

PLOTTED BY: fkonopka
 PLOTTED FROM: i:\users\bkruse\p\d\09864\09864gbb.dgn
 09864GBB.DGN
 PLOT SUBMITTED: 09-OCT-1998 09:10

DRIVES													
REFERENCE NO.	PLAN SHEET NO.	LOCATION	SIDE	WIDTH	LENGTH	EXIST. DRIVEWAY	202	255	203	301	448	452	452
							PAVEMENT REMOVED SQ. YD.	FULL DEPTH PAVEMENT SAWING LIN. FT.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION CU. YD.	BITUMINOUS AGGREGATE BASE, P664-22 CU. YD.	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, P664-22 (DRIVEWAYS) CU. YD.	6" PLAIN CONCRETE PAVEMENT SQ. YD.	8" PLAIN CONCRETE PAVEMENT SQ. YD.
106DR	39	229+58	RT.	49.0	5.0	ASP.					0.95		
107DR	"	234+94	RT.	56.0	12.0	CON.	74.7						74.7
108DR	40	241+97	RT.	40.0	7.0	CON.	31.3	36.0					31.3
109DR	"	247+15	RT.	18.0	7.0	CON.	14.0					14.0	
110DR	"	248+11	RT.	19.0	5.0	ASP.					0.37		
111DR	"	248+68	RT.	22.0	5.0	ASP.					0.42		
112DR	41	250+07	RT.	20.0	5.0	ASP.					0.39		
113DR	"	252+48	RT.	27.0		CON.	(NO WORK)						
114DR	"	253+23	RT.	19.0	5.0	ASP.					0.37		
115DR	"	254+21	RT.	29.0	5.0	ASP.					0.56		
116DR	"	255+84	RT.	21.0	5.0	ASP.					0.41		
117DR	"	256+33	RT.	31.0	11.0	CON.	37.9					37.9	
118DR	42	259+18	RT.	21.0	10.0	CON.	23.3					23.3	
119DR	"	259+63	RT.	21.0	9.0	CON.	21.0					21.0	
120DR	"	262+62	RT.	28.0	5.0	ASP.					0.54		
121DR	"	264+16	RT.	21.0	5.0	ASP.					0.41		
122DR	"	264+83	RT.	42.0	5.0	ASP.					0.81		
123DR	"	266+21	LT.	69.0	5.0	ASP.					1.33		
124DR	43	269+20	LT.	37.0	7.0	CON.	28.8						28.8
125DR	"	270+12	RT.	19.0	5.0	ASP.					0.37		
126DR	"	271+25	RT.	26.0	5.0	ASP.					0.50		
127DR	"	272+45	RT.	19.0	5.0	ASP.					0.37		
128DR	"	272+85	RT.	18.0	5.0	ASP.					0.34		
129DR	"	273+28	LT.	21.0	5.0	ASP.					0.41		
130DR	"	274+68	LT.	20.0	10.0	CON.	22.2					22.2	
131DR	"	275+16	RT.	20.0	5.0	GRA.			1.5	1.16	0.39		
132DR	"	276+00	RT.	28.0	5.0	ASP.					0.54		
133DR	"	277+83	LT.	22.0	5.0	GRA.			1.7	1.27	0.42		
134DR	44	279+79	LT.	23.0	5.0	ASP.					0.44		
135DR	"	282+06	LT.	20.0	5.0	ASP.					0.39		
136DR	"	283+51	LT.	21.0	5.0	ASP.					0.41		
137DR	"	284+27	LT.	31.0		CON.	(NO WORK)						
138DR	"	285+44	LT.	22.0	5.0	ASP.					0.42		
139DR	"	287+75	LT.	27.0	5.0	ASP.					0.52		
140DR	45	290+66	RT.	86.0	13.0	CON.	124.2						124.2
141DR	"	292+28	LT.	63.0	5.0	CON./ASP.				1.22			
142DR	"	295+98	RT.	42.0	8.0	CON.	37.3					37.3	
143DR	"	296+38	LT.	31.0	8.0	CON.	27.6					27.6	
144DR	"	297+21	RT.	58.0	13.0	CON.	83.8					83.8	
145DR	"	297+34	LT.	27.0	7.0	CON.	21.0					21.0	
146DR	"	297+79	LT.	48.0	7.0	CON.	37.3					37.3	
147DR	46	299+28	RT.	59.0	13.0	CON.	85.2					85.2	
148DR	"	299+37	LT.	57.0	7.0	CON.	44.3					44.3	
SUB-TOTALS(C)							713.9	36.0	3.2	2.43	13.30	454.9	259.0
SUB-TOTALS(A)(FROM SHT 22)							726.2	104.0	16.9	12.70	14.13	347.2	379.0
SUB-TOTALS(B)(FROM SHT 22)							250.5	97.0	19.1	8.39	16.92	58.3	154.6
TOTALS							1690.6	237.0	39.2	23.52	44.35	860.4	792.6
TOTALS (TO GENERAL SUMMARY)							1691	237	39	24	44	860	793

WALK											
REFERENCE NO.	PLAN SHEET NO.	LOCATION	SIDE	202	608						
				WALK REMOVED SQ. FT.	4" CONCRETE WALK SQ. FT.	CURB RAMP, TYPE 1 EACH	CURB RAMP, TYPE 2 EACH	CURB RAMP, TYPE 1 SQ. FT.	CURB RAMP, TYPE 2 SQ. FT.		
1-CR	26	99+75	LT.		50						
2-CR	"	100+30	LT.		50						
3-CR	"	100+30	RT.		50						
4-CR	27	110+22	LT.		50						
5-CR	"	110+67	LT.		50						
6-CR	29	127+93	LT.		50						
7-CR	"	129+03	LT.		50						
8-CR	30	138+75	RT.		50						
9-CR	"	139+20	RT.		50						
10-CR	"	144+03	RT.		50						
11-CR	"	144+46	RT.		50						
12-CR	31	152+79	RT.		50						
13-CR	"	153+22	RT.		50						
14-CR	32	164+01	LT.		75						
15-CR	"	164+21	RT.		75						
16-CR	"	165+08	LT.		50						
16A-CR	"	165+18	LT.		50						
16B-CR	"	165+18	RT.		130						
17-CR	"	165+65	RT.		50						
18-CR	33	171+38	LT.		75						
19-CR	"	172+08	RT.		75						
20-CR	"	172+37	LT.		50						
20A-CR	"	172+82	RT.		183						
21-CR	"	173+10	RT.		50						
22-CR	35										
23-CR	"										
24-CR	"	194+44	RT.		50						
25-CR	"	194+86	RT.		50						
26-CR	39	231+35	LT.	50							50
27-CR	42	265+92	LT.	50							50
28-CR	"	266+49	LT.	50							50
31-CR	43	270+82	LT.	50							50
32-CR	"	271+35	LT.	50							50
33-CR	44	286+52	RT.		50						
34-CR	"	287+12	RT.		50						
35-CR	45	290+39	RT.	50							50
36-CR	"	290+92	RT.	50							50
TOTALS (TO GEN. SUMMARY)				1475	1713	4	27				350

CALCULATED
 EMK
 CHECKED
 ENF
 DRIVE AND WALK QUANTITIES
 CUYAHOGA COUNTY
 LAKE COUNTY
 CUY/LAK-91-15.42/0.00
 23
 104