

GENERAL NOTES

LAKE COUNTY
LAK-91-(4.23)(4.49)

OHIO
FHWA
REGION 5

35
56

FIELD BONDING

IMMEDIATELY PRIOR TO ADHESIVE APPLICATION, BONDING SURFACES SHALL BE CLEAN, DRY AND WARMER THAN 45F AND SHALL BE MAINTAINED ABOVE 45F UNTIL THE ADHESIVE HAS CURED.

ADHESIVE COMPONENTS SHALL BE COMBINED IN THE EXACT RATIOS RECOMMENDED BY THE ADHESIVE MANUFACTURER AND SHALL BE CAREFULLY AND THOROUGHLY MIXED TO ENSURE A UNIFORM MATERIAL FREE FROM ENTRAPPED AIR. THE BONDING PROCEDURES AND RATE OF APPLICATION SHALL BE IN ACCORDANCE WITH THE ADHESIVE MANUFACTURER'S INSTRUCTIONS AND RECOMMENDATIONS. FOR PROPER CONTROL DURING CURING, LIGHT PRESSURE SHOULD BE MAINTAINED UNTIL THE ADHESIVE HAS CURED.


MEASUREMENT AND PAYMENT

RAISED CONCRETE MEDIAN SEAL WILL BE MEASURED BY THE LINEAR FOOT COMPLETED IN PLACE AND PAID FOR AT THE CONTRACT UNIT PRICE BID PER LINEAR FOOT FOR ITEM 516, STRUCTURAL JOINT OR JOINT SEALER, MISC. RAISED CONCRETE MEDIAN SEAL. THIS PRICE SHALL BE PAYMENT IN FULL FOR FURNISHING ALL MATERIALS, EQUIPMENT AND LABOR TO COMPLETE THE WORK AS SPECIFIED. LABOR TO COMPLETE THE WORK AS SPECIFIED.


ITEM SPECIAL - SEALING OF CONCRETE SURFACES:

A CONCRETE SEALER SHALL BE APPLIED TO THE FOLLOWING CONCRETE SURFACES: SEE SHEET 5/24 AND 6/24, TYPICAL TRANSVERSE MODIFIED DECK SECTIONS, SHEET 23/24, PIER SECTION AND ABUTMENT WINGWALL ELEVATION. SEE THE PROPOSAL NOTE FOR SURFACE PREP REQUIREMENTS, APPLICATION RATES, MATERIAL REQUIREMENTS AND APPLICATION PROCEDURES.

E:\PR1608\NOTE\PILOT SCALE 14\PILOT DATE 1-17-91

Burgess & Niple, Limited  4 / 24
Engineers and Architects

GENERAL STRUCTURE NOTES
BRIDGE NO. LAK - 91 - 0423
BRIDGE NO. LAK - 91 - 0449

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED DATE	REVISED
	SJS TPM		WAC	2-27-92	