

GENERAL SUMMARY

CALCULATED
K. L. ST.
REVISED
05/01/94
11-94

SHEET NUMBER												ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	AS PER PLAN DESIGNATION	
4	6	8	9	15	16	17	30	31	32								
												ROADWAY					
												201	11000	LUMP	CLEARING AND GRUBBING		
					300.0	137.5	262.5					202	4000	LUMP	REMOVING OF STRUCTURE REMOVED		
												202	38001	700.0	LIN.FT.	GUARDRAIL REMOVED, AS PER PLAN	
					237	188	189					203	12000	614	CU.YD.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	
					66	19	32					203	20000	102	CU.YD.	EMBANKMENT	
					300.0	137.5	262.5					606	13050	700.0	LIN.FT.	GUARDRAIL, TYPE 5A	
					56							609	26000	56	LIN.FT.	CURB, TYPE 6	
5												616	10000	5	M.GAL.	WATER	
1												616	20000	1	TON	CALCIUM CHLORIDE	
	28											626	00100	28	EACH	BARRIER REFLECTOR, TYPE A	
												EROSION CONTROL					
245												207	10000	245	SQ.YD.	TEMPORARY SEEDING AND MULCHING	
800												207	30000	200	LIN.FT.	FILTER FABRIC FENCE	
50												207	70000	50	EACH	STRAW OR HAY BALES	
					539	305	382					659	10000	1,226	SQ.YD.	SEEDING AND MULCHING	
61												659	14000	61	SQ.YD.	REPAIR SEEDING AND MULCHING	
0.01					0.05	0.03	0.03					659	20000	0.12	TON	COMMERCIAL FERTILIZER	
					0.24	0.14	0.17					659	30000	0.55	TON	AGRICULTURAL LIMING	
2					1	1	1					659	35000	5	M-GAL.	WATER	
												MAINTENANCE OF TRAFFIC					
	50											410	12000	50	CU.YD.	TRAFFIC COMPACTED SURFACE, TYPE A OR B	
			152									614	12800	152	EACH	TEMPORARY RAISED PAVEMENT MARKER	
	5											614	13000	5	CU.YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
				79								614	13302	71	EACH	BARRIER REFLECTOR, TYPE B2	
				141								614	13350	141	EACH	OBJECT MARKER	
				0.06								614	21000	0.06	MILE	TEMPORARY CENTER LINE, CLASS I	
	0.5											614	21400	0.5	MILE	TEMPORARY CENTER LINE, CLASS II	
				0.27								614	22000	0.27	MILE	TEMPORARY EDGE LINE, CLASS I	
	10											616	10000	10	M.GAL.	WATER	
	1											616	20000	1	TON	CALCIUM CHLORIDE	
				1,404								622	40020	1,404	LIN.FT.	PORTABLE CONCRETE BARRIER, 32"	
												TRAFFIC					
	0.8											642	00102	0.8	MILE	EDGE LINE, TYPE 2	
	0.4											642	00302	0.4	MILE	CENTER LINE, TYPE 2	
												PAVEMENT					
					335							407	10000	335	GAL.	TACK COAT	
					155							44B	47010	155	CU.YD.	ASPHALT CONCRETE SURFACE COURSE, TYPE I, PG64-28	

GENERAL SUMMARY

LAK - 174 - 4.39

DATE: 09-19-96 - TIME: 14:39 - H:\CT\9319\CA02\9319404.DWG