

GENERAL SUMMARY

CALCULATED
11-94
CHECKED
D.J.W.
11-94

SHEET NUMBER														ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	AS PER PLAN DESIGNATION
4	6	8	9	15	16	17	30	31	32									
STRUCTURE																		
								61	57	53	503	21101	171	CU.YD.	UNCLASSIFIED EXCAVATION, AS PER PLAN			
								480	195	420	524	94601	1,095	LIN.FT.	DRILLED SHAFT, 30" DIAMETER, AS PER PLAN	4		
								97	39	85	511	46000	221	CU.YD.	CLASS C CONCRETE, RETAINING WALL			
								45,049	16,741	37,357	513	11100	99,147	POUND	STRUCTURAL STEEL, AISC CATEGORY I			
								896	364	784	513	20000	2,044	EACH	WELDED STUD SHEAR CONNECTOR			
								279	108	243	SPECIAL	6018000	630	EACH	SPECIAL-MISC: 4" X 12" X 7'-10" TIMBER	5		
								855	300	750	SPECIAL	6018200	1905	SQ.FT.	SPECIAL-MISC: PREFABRICATED GEOCOMPOSITE IN PLANE DRAIN	5		
											614	11000	LUMP		MAINTAINING TRAFFIC			
											619	16010	7	MONTH	FIELD OFFICE, TYPE B			
											SPECIAL	6026010	7	MONTH	COMPUTER EQUIPMENT FOR TYPE B OR C OFFICE			
											623	10000	LUMP		CONSTRUCTION LAYOUT STAKES			
											624	10000	LUMP		MOBILIZATION			

GENERAL SUMMARY

LAK - 174 - 4.39