GENERAL SUMMARY

(A)-City of Euclid
(B)-City of Wickliffe
(C)-City of Willowick
(D)-City of Eastlake
(E)-City of Willoughby
(F)-City of Mentor

FHWA REGION	STATE	PROJECT	
5	OHIO		

LAKE COUNTY
LAK-2-0.00

30
171

⊗ 250' STATE AND LOCAL PARTICIPATION
* STATE AND LOCAL PARTICIPATION ONLY

ITEM	SHEET NUMBER: GENERAL NOTES A	B	C	D	E	F	19 E	21 A	B	D	E	54 B	C	D	E	46 E	CITY TOTALS: Euclid	Wickliffe	Willowick	Eastlake	Willoughby	Mentor	ITEM	QUANT.	UNIT	DESCRIPTION
																										DRAINAGE
602											1.37										1.37		602	1.37	C.Y.	CONCRETE MASONRY
603											11										11		603	11	L.F.	12" CONDUIT, TYPE B
603		150	40	140	170						20							150	40	140	190		603	520⊗	L.F.	6" CONDUIT, TYPE F
603								10	26	6							10	26		6			603	42	L.F.	15" CONDUIT, TYPE C
603											6										6		603	6	L.F.	15" CONDUIT, TYPE C, AS PER PLAN, 706.01, 706.02
603										16										16			603	16	L.F.	21" CONDUIT, TYPE C, 706.01, 706.02
603											33										33		603	33	L.F.	30" CONDUIT, TYPE A, AS PER PLAN, 706.02
604											1										1		604	1	EACH	CATCH BASIN, STANDARD № 2-2-B
604									1	1								1		1			604	2	EACH	MANHOLE STANDARD NO. 1
604								1									1						604	1	EACH	CATCH BASIN, STANDARD № 4
604									1	3								1		3			604	4	EACH	CATCH BASIN, STANDARD № 5
604								1									1						604	1	EACH	MANHOLE, RECONSTRUCTED TO GRADE
604										1										1			604	1	EACH	CATCH BASIN RECONSTRUCTED TO GRADE
605		130	50	140	180													130	50	140	180		605	500*	L.F.	6" UNCLASSIFIED PIPE UNDERDRAINS
605		75	20	70	85													75	20	70	85		605	250	L.F.	AGGREGATE DRAIN
605							650									341					991		605	991	L.F.	6" SHALLOW PIPE UNDERDRAIN
605												2500	650	2200	2500			2500	650	2200	2500		605	7850	L.F.	LONGITUDINAL AGGREGATE DRAINS, AS PER PLAN
605												900	200	800	850			900	200	800	850		605	2750	L.F.	TRANSVERSE AGGREGATE DRAINS, AS PER PLAN
SPEC		110	40	110	135													110	40	110	135		SPEC.	395*	EACH	UNDERDRAIN OPENING
SPEC		50	20	55	70													50	20	55	70		SPEC	195*	MGAL	WATER
SPEC	35	225	55	200	275	10											35	225	55	200	275	10	SPEC	800	HOURS	LAW ENFORCEMENT OFFICER WITH PATROL CAR
614																							614	LUMP		MAINTAINING TRAFFIC
619																							619	LUMP		FIELD OFFICE
623																							623	LUMP		CONSTRUCTION LAYOUT STAKES
624																							624	LUMP		MOBILIZATION

FOR TRAFFIC CONTROL GENERAL SUMMARY, SEE SHEET 28, 115, 116 & 117
FOR LIGHTING, GENERAL SUMMARY, SEE SHEET 144