

GENERAL SUMMARY

TRAFFIC CONTROL

- Ⓐ - CITY OF EUCLID
- Ⓑ - CITY OF WICKLIFFE
- Ⓒ - CITY OF WILLOWICK
- Ⓓ - CITY OF EASTLAKE
- Ⓔ - CITY OF WILLOUGHBY
- Ⓕ - CITY OF MENTOR

FEMA REGION	STATE	PROJECT	
5	OHIO		

LAKE COUNTY
LAK-2-0.00

115
171

ITEM	94 & 95				97				98 & 102	98 & 104	99 & 104	100 & 106	101 & 109	101 & 109	CITY TOTALS					ITEM	QUANT.	UNIT	DESCRIPTION			
	Ⓑ	Ⓒ	Ⓓ	Ⓔ	Ⓑ	Ⓒ	Ⓓ	Ⓔ	Ⓐ	Ⓑ	Ⓒ	Ⓓ	Ⓔ	Ⓕ	EUCLID	WICK-LIFFE	WILLO-WICK	EAST-LAKE	WILL-OUGHBY					MENTOR		
TRAFFIC CONTROL (Continued from sheet 28)																										
620	165	33	120	196												165	33	120	196				620	514	EACH	DELINEATOR, TYPE C, FLEXIBLE POST MOUNTED
620	4	1	7	6												4	1	7	6				620	18	EACH	DELINEATOR, TYPE C, BRACKET MOUNTED
620	56	34	61	112												56	34	61	112				620	263	EACH	DELINEATOR, TYPE D, FLEXIBLE POST MOUNTED
621								0.06	10.47	3.20	9.80	12.95	0.13		0.06	10.47	3.20	9.80	12.95	0.13		621	36.61	MILES	EDGE LINE	
621								0.06	8.08	1.88	7.54	5.40	0.06		0.06	8.08	1.88	7.54	5.40	0.06		621	23.02	MILES	LANE LINE	
621									3004	1077	4218	3480				3004	1077	4218	3480			621	11779	L.F.	CHANNELIZING LINE	
621									103	30	310	205				103	30	310	205			621	648	L.F.	STOP LINE	
621									656	345	656	474				656	345	656	474			621	2131	L.F.	TRANSVERSE LINE	
621									30							30						621	30	S.F.	ISLAND MARKING	
621									10	4	15	10				10	4	15	10			621	39	EACH	LANE ARROW	
621									5	2	8	5				5	2	8	5			621	20	EACH	WORD "ONLY" ON PAVEMENT 72 INCH	
621									103	239	90	302				103	239	90	302			621	734	L.F.	CROSSWALK LINE	
SPECIAL					862	269	954	995								862	269	954	995			SPECIAL	3080	EACH	RAISED PAVEMENT MARKER	
630									507.6	173.3	499.4	615.3				508.0	173.3	499.4	615.3			630	1796	S.F.	SIGN, FLAT SHEET, TYPE G SHEETING	
630									30	30	60	30				30	30	60	30			630	45	L.F.	ONE WAY SUPPORT NO 4 POST	
630									298	244	527	477				298	244	527	477			630	150	L.F.	ONE WAY SUPPORT NO 3 POST	
630									542	77	284	481				542	77	284	481			630	1546	L.F.	GROUND MOUNTED SUPPORT, NO 3 POST	
630									217	35	209	338				217	35	209	338			630	1384	L.F.	GROUND MOUNTED SUPPORT, NO 4 POST	
630									47	126	43	43				47	126	43	43	34		630	799	L.F.	GROUND MOUNTED SUPPORT, S4 x 7.7 BEAM	
630									47							47					34	630	204	L.F.	GROUND MOUNTED SUPPORT, W6 x 9 BEAM	
630									47							47						630	259	L.F.	GROUND MOUNTED SUPPORT, W10 x 12 BEAM	
630								47	47						47	47						630	94	L.F.	GROUND MOUNTED SUPPORT, W8 x 18 BEAM	
630									5							5						630	5	EACH	SIGN ATTACHMENT ASSEMBLY	
630												3							3			630	3	EACH	SIGN SUPPORT ASSEMBLY, POLE MOUNTED	
630								2.20	5.44	7.14	6.88	9.58	0.66		2.20	5.44	7.14	6.88	9.58	0.66		630	31.90	C.Y.	CONCRETE FOR EMBEDDED FOUNDATION	
630								2	14	8	18	28	2		2	14	8	18	28	2		630	72	EACH	BREAKAWAY BEAM CONNECTION	
630								1	63	17	62	51	4		1	63	17	62	51	4		630	198	EACH	REMOVAL OF GROUND MOUNTED SIGN AND STORAGE	
630								1	84	26	83	79	4		1	84	26	83	79	4		630	277	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT	