

GENERAL SUMMARY

- (A) - City of Euclid
- (B) - City of Wickliffe
- (C) - City of Willowick
- (D) - City of Eastlake
- (E) - City of Willoughby
- (F) - City of Mentor

FHWA REGION	STATE	PROJECT	
5	OHIO		

117
171

LAKE COUNTY
LAK-2-000

* STATE & LOCAL PARTICIPATION

ITEM	SHEET				NUMBER				CITY TOTALS						ITEM	QUANT	UNIT	DESCRIPTION
	93	93	93	93					City of Euclid	City of Wickliffe	City of Willowick	City of Eastlake	City of Willoughby	City of Mentor				
	B	C	D	E	B	C	D	E										
625					6	3	7	10							625	26	EACH	GROUND ROD
631					6	5	7	10							631	28	EACH	DISCONNECT SWITCH WITH ENCLOSURE, TYPE 'X'
631					3	5	5	4							631	17	EACH	SWITCH ENCLOSURE MOUNTING BRACKET ASSEMBLY
631					12	5	13	14							631	44	EACH	SIGNS WIRED
631						2									631	2	EACH	SIGNS WIRED, OVERPASS STRUCTURE MOUNTED
631					6	5	7	10							631	28	EACH	SIGN SERVICE
631						2		3							631	5	EACH	MERCURY VAPOR LUMINAIRE, TYPE TC 31.21, WITH 100 WATT LAMP
631					21	7	19	16							631	63	EACH	MERCURY VAPOR LUMINAIRE, TYPE TC 31.21, WITH 175 WATT LAMP
631							2	2							631	4	EACH	MERCURY VAPOR LUMINAIRE, TYPE TC 31.21, WITH 250 WATT LAMP
631						2		3							631	5	EACH	BALLAST, TYPE CMRI-100, 480 VOLT
631					21	7	19	16							631	63	EACH	BALLAST, TYPE CMRI-175, 480 VOLT
631							2	2							631	4	EACH	BALLAST, TYPE CMRI-250, 480 VOLT
631					3	1	3	2							631	9	EACH	BALLAST ENCLOSURE, TYPE 'A'
631					3	4	4	9							631	20	EACH	BALLAST ENCLOSURE, TYPE 'B'
631					3	5	5	5							631	18	EACH	BALLAST ENCLOSURE MOUNTING BRACKET
631								2							631	3	EACH	PHOTOELECTRIC CONTROL
631					10	5	14	8							631	37	EACH	REMOVAL OF DISCONNECT SWITCH ENCLOSURE
631					10	5	14	8							631	37	EACH	REMOVAL OF BALLAST WIRING ENCLOSURE
					33	13	39	21							631	106	EACH	REMOVAL OF FLUORESCENT LIGHTING FIXTURES INCLUDING LAMPS
632	75	20	70	85											632	250	LIN. FT.	LOOP DETECTOR PAVEMENT CUTTING
632	150	40	140	170											632	500	LIN. FT.	LOOP DETECTOR WIRE