LIGHTING QUANTITIES SUB-SUMMARY

LAKE COUNTY
LAK-2-0.00

FHWA REGION	STATE	PROJECT	
5	OHIO		

REF. NO.	STATION TO STATION	SIDE	625 LIGHT TOWER BBBBO 713.21	625 LIGHT TOWER BBBB100 713.21	625 LIGHT TOWER BBBBBBB110 713.21	625 LIGHT TOWER BBBBBBB100 713.21	202 PULLBOX ABANDONED	202 LIGHT POLE REMOVED	625 LUMINAIRE, LIGHT TOWER, TYPE I, 400 WATT HPS, 713.21	625 LUMINAIRE, LIGHT TOWER, ASYMMETRIC, 400 WATT HPS, 713.21	625 LUMINAIRE, LIGHT TOWER, SYMMETRIC 400 WATT HPS, 713.21	625 LUMINAIRE, UNDERPASS, 100 WATT HPS 713.13	625 LIGHT TOWER FOUNDATION 36"X20' DEEP	625 LIGHT TOWER FOUNDATION 36"X25' DEEP	625 LIGHT MAINT. PLATFORM, TYPE C	625 STRUCTURE GROUNDING SYSTEM	625 TRENCH, AS PER PLAN	625 MEDIAN PULLBOX MODIFIED A AS PER PLAN	625 MEDIAN PULLBOX MODIFIED B AS PER PLAN	625 GROUND ROD 713.16	625 PULLBOX CONCRETE 24"	625 PULLBOX CONCRETE 18"	625 TRENCH, 24" DEEP			625 CONDUIT, 3" - 713.04	625 CONDUIT, 2" 713.04	625 NO. 4 AWG 5000 VOLT DISTRIBUTION CABLE	625 1 1/2" DUCT CABLE WITH 2 NO. 4 AWG 5000 VOLT CABLES	625 CABLE SPLICING KIT	SPEC PLASTIC CAUTION TAPE	625 CONDUIT 2" 713.04 AS PER PLAN	625 POWER SERVICE		SPECIAL CONNECTOR KIT TYPE VII A	SPECIAL CONNECTOR KIT TYPE VII B	SPECIAL CONNECTOR KIT TYPE VII C	SPECIAL PORTABLE POWER UNIT	SPECIAL TOWER LIGHTNING PROTECTION SYSTEM	SPECIAL POWER CONNECTION	SPECIAL SERVICE TO UNDERPASS LIGHTING SYSTEM BRIDGE LAK-2-0399L	SPECIAL SERVICE TO UNDERPASS LIGHTING SYSTEM BRIDGE LAK-2-0399L	SEE SHEET NO.
			EA		EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	LF	EA	EA	EA	EA	EA	LF			LF	LF	LF	LF	EA	LF	LF	EA		EA	EA	EA	EA	EA	EA	LUMP	LUMP	
	WILLOUGHBY (CONT'D)																																										
	196 + 00 (90)		1						3				1					1		2			2			2			380													
	196+00 - 197+80 M/L	℄ - ℄																																									
	197+80 - 9+00 E-3	℄ - LT															36	1			1	440	70			490																	
	197+80 -200+43	℄																											546													
	200 + 43 (91)	℄	1						3				1					1		2			2			2																	
	200+43 -204+66	℄																											866													
	204 +66 (92)	℄	1						3				1					1		2			2			2																	
	204+66 - 208+95	℄																											878													
	208 + 95 (93)	℄	1						3				1					1		2			2			2																	
	208+95 - 213 + 21	℄																											872													
	213 + 21 (94)	℄	1						3				1					1		2			2			2																	
	213+21 - 217 + 81	℄																											940													
	217 + 81 (95)	℄	1						3				1					1		2			2			2																	
	TOTALS SHEET 157		6						18				6				36	6		12		1	452			82		4482	610					4	10			5				
	TOTALS-CITY OF WILLOUGHBY		24	10		2	1		84	40	6	12	24	13	2	3	395	36	1	80	2	21	8,169			951	140	28044	10875	48	290	595	2		40	48	2	1	36	4	LUMP	LUMP	
	S-TOTAL																																									
	TOTAL																																									

LD 0301
12-29-67

LIGHTING SUB - SUMMARY