



WATER MAIN	
VALVE BOX ADJUSTED TO GRADE	14 EA.
MANHOLE CASTING ADJUSTED TO GRADE	3 EA.
TEE PLUGGED AT MAIN	2 EA.
HYDRANT ABANDONED	1 EA.
6" WATER LINE REMOVED	70 L.F.

MONUMENT BOXES		
Ref. No.	Location	I-8 Mon. Boxes Adjusted to Grade Each
I-M	18+02.48	1

UNDERDRAINS			
From	To	Side	I-4 6" Underdrain Lin. Ft.
10+00	16+00	L	596
18+20	23+00	R	120

STORM SEWERS							
Ref. No.	Location		Side	I-8 M.H. Adjust to Grade Each	I-16 C.B. Abandon Each	I-8 Std. #1-2A C.B. with Salv. Casting Each	I-2 12" Class "A" Lin. Ft.
	From	To					
I-8	10+00	23+00	L/R	10	3	1	20
TOTALS				10	4	1	20

PAVEMENT QUANTITIES							
STATIONS	PORTLAND CEMENT CONCRETE BASE COURSE		CRUSHED EXIST. PAVT. EXIST. CURB COURSE		ASPHALTIC CONCRETE COURSE		T-30 ASPHALTIC BITUMIN. TRACK COAT
	FROM	TO	SQ. YDS.	CU. YDS.	SQ. YDS.	CU. YDS.	CU. YD.
10+00	16+00	606	115	86	83	95	240
16+00	23+00	972	163	53	143	156	413
TOTALS		1578	280	139	226	251	653

* INCLUDES EXTRA LEVELING...
100 CU.YD./MILE X .246 MI. = 25 CU.YD.