SUB SUMMARY

COMPUTED BY: D.J.W. 5-81
CHECKED BY: R.A.S. 1/83

FHWA REGION	STATE	PROJECT		
5	OHIO			

9
39

LAKE COUNTY
LAK-2/91-0.31/4.56

690

FOR BRIDGE DECK REPAIR DETAILS SEE SHEET NO. 37
FOR TRAFFIC CONTROL SEE SHEET NO. 20 THRU 36

	BRIDGE NO.	202 WEARING COURSE REMOVED	202 PORTIONS OF STRUCTURE REMOVED	516 EXPANSION JOINT MODIFIED, AS PER PLAN	509 REINFORCING STEEL	511 CLASS "S" CONCRETE, SUB-STRUCTURE	516 VERTICAL EXTENSION OF STRUCTURAL EXPANSION JOINTS, AS PER PLAN	516 ELASTOMERIC COMPRESSION SEALS FOR CONCRETE SLAB BRIDGE JOINTS, AS PER PLAN.	404 ASPHALT CONCRETE AC-20	605 AGGREGATE DRAIN	407 TACK COAT	407 COVER AGGREGATE	845 LATEX MODIFIED CONCRETE OVERLAY 1¼" THICKNESS	845 LATEX MODIFIED CONCRETE OVERLAY VARIABLE THICKNESS	845 FULL DEPTH REPAIR ++	845 LATEX MODIFIED CONCRETE OVERLAY 2" THICKNESS	SPECIAL PRESSURE RELIEF JOINT, TYPE C	SPECIAL SEALING OF CONCRETE SURFACES	516 EXPANSION JOINT REBUILT, AS PER PLAN	SPECIAL PATCHING CONCRETE STRUCTURES WITH MAGNESIUM PHOSPHATE CONCRETE
		SQ. YDS.	LUMP	L.F.	LBS.	CU. YDS.	LIN. FT.	LIN. FT.	C.Y.	LIN. FT.	GALS.	TONS	SQ. YDS.	CU. YDS.	CU. YDS.	SQ. YDS.	LIN. FT.	SQ. YD.	L.F.	SQ. FT.
CITY OF WICKLIFFE	LAK-2-0031 L	1713						132	15		70	2.5	1023	77	2			865		150
	LAK-2-0031 R	1520						108	15		70	2.5	830	62	2			800		150
	LAK-2-0055 L	1838		130					15		70	2.5	1148	86	2			815		150
	LAK-2-0055 R	1492		105					12		57	2.0	932 ?	70	2			785		150
	LAK-2-0105 L	1445						108	15		70	2.5	755	57	2			660		150
	LAK-2-0105 R	1445						108	15		70	2.5	755	57	2			665		150
CITY OF WILLOWICK	LAK-2-0180 L		LUMP See Sht 37		716	24							NO	OVERLAY	REQUIRED			850	104	80
	LAK-2-0180 R		LUMP See Sht 37		716	24							NO	OVERLAY	REQUIRED			815	104	80
CITY OF EASTLAKE	LAK-2-0255 L	1520					125		15		70	2.5	830	62	2			865		50
	LAK-2-0255 R	1520					125		15		70	2.5	830	62	2			860		50
	LAK-2-0303 L	948						163	16		74	2.5	213 ?	16	2			195		20
	LAK-2-0303 R	1034						180	17		80	3.0	234 ?	18	2			195		20
	LAK-2-0363 L												NO	WORK	REQUIRED					
	LAK-2-0363 R												NO	WORK	REQUIRED					
CITY OF WILLOUGHBY	LAK-2-0399 L						145		12		57	2.0	1283	64	2			910		130
	LAK-2-0399 R	1843					145		12		57	2.0	1283 ?	96	2			910		130
	LAK-2-0486 L							93	9		43	1.5	638	32	2			650		400
	LAK-2-0486 R							93	9		43	1.5	638	21	2			655		400
	LAK-2-0530 L												NO	WORK	REQUIRED					
	LAK-2-0530 R												NO	WORK	REQUIRED					
CITY OF MENTOR	LAK-2-0760 L							84	9		43	1.5	315	25	2			160		40
	LAK-2-0760 R	740							9		43	1.5		35	2	315		160		40
	LAK-2-0954 L												NO	WORK	REQUIRED					
	LAK-2-0954 R												NO	WORK	REQUIRED					
	LAK-2-1169 L							84	9		43	1.5	236	6	2			155		40
	LAK-2-1169 R							84	9		43	1.5	236	6	2			155		40
	LAK-2-1350												NO	WORK	REQUIRED					
	LAK-2-1351												NO	WORK	REQUIRED					
CITY OF EASTLAKE	LAK-91-0456	2700					170		16	40	71	2.5	2040	153	2		145	2115		60
CITY OF WILLOUGHBY	LAK-2-0543		LUMP See Sht 37		1090	36				40			NO	OVERLAY	REQUIRED		102	1975	125	80
CITY OF MENTOR	LAK-2-1262						155		16	60	68	2.5	2171	127	2		108	1820		60
	TOTAL	19,758	LUMP	235	2,522	84	865	1237	260	140	1212	43	16300	1132	40	315	355	18035	333	2620

++ SUBJECT TO NON-PERFORMANCE IF NOT REQUIRED