

# ESTIMATED QUANTITIES

□ EACH PAY LINEAR FOOT OF GRINDING FLANGE EDGES INCLUDES THE GRINDING OF ALL FOUR FLANGE EDGES ON THE ONE LINEAR FOOT OF FLANGE.

\* AS DIRECTED BY THE ENGINEER

ITEM	ITEM EXT.	DESCRIPTION	TOTAL	UNIT	①	②	③	④	⑤	⑥
					LAK-2-0055L LLOYD RD RAMP UNDER SR-2	LAK-2-0055R LLOYD RD RAMP UNDER SR-2	LAK-2-0180L E 305TH ST UNDER SR-2	LAK-2-0180R E 305TH ST UNDER SR-2	LAK-2-0255L E 337TH ST UNDER SR-2	LAK-2-0255R E 337TH ST UNDER SR-2
815	00050	SURFACE PREPARATION OF EXISTING STEEL, SYSTEM OZEU	247789	S.F.	16059	16059	12860	12860	11209	11209
815	00056	FIELD PAINTING OF EXISTING STEEL, PRIME COAT, SYSTEM OZEU	247789	S.F.	16059	16059	12860	12860	11209	11209
815	00060	FIELD PAINTING OF EXISTING STEEL, INTERMEDIATE COAT, SYSTEM OZEU	247789	S.F.	16059	16059	12860	12860	11209	11209
815	00066	FIELD PAINTING OF EXISTING STEEL, FINISH COAT, SYSTEM OZEU	247789	S.F.	16059	16059	12860	12860	11209	11209
815	00050	SURFACE PREPARATION OF EXISTING STEEL, SYSTEM OZEU, O.B.T.	411	S.F.						
815	00056	FIELD PAINTING OF EXISTING STEEL, PRIME COAT, SYSTEM OZEU, O.B.T.	411	S.F.						
815	00060	FIELD PAINTING OF EXISTING STEEL, INTERMEDIATE COAT, SYSTEM OZEU, O.B.T.	411	S.F.						
815	00066	FIELD PAINTING OF EXISTING STEEL, FINISH COAT, SYSTEM OZEU, O.B.T.	411	S.F.						
815	00050	SURFACE PREPARATION OF EXISTING STEEL, SYSTEM OZEU, E.O.G.	8	S.F.						
815	00056	FIELD PAINTING OF EXISTING STEEL, PRIME COAT, SYSTEM OZEU, E.O.G.	8	S.F.						
815	00060	FIELD PAINTING OF EXISTING STEEL, INTERMEDIATE COAT, SYSTEM OZEU, E.O.G.	8	S.F.						
815	00066	FIELD PAINTING OF EXISTING STEEL, FINISH COAT, SYSTEM OZEU, E.O.G.	8	S.F.						
815	00500	* CAULKING	50	L.F.						
815	00504	* GRINDING FINS, TEARS, SLIVERS	85	M.H.						
815	00508	□ GRINDING FLANGES EDGES	19969	L.F.	1449	1449	1123.5	1123.5	1001	1001
SPECIAL	10000300	PREMIUM ON RAILROAD'S PROTECTIVE PUBLIC LIABILITY * AND PROPERTY DAMAGE LIABILITY INSURANCE	LUMP							
614	11000	MAINTAINING TRAFFIC	LUMP							
SPECIAL	614E11100	LAW ENFORCEMENT OFFICER WITH PATROL CAR	1067	M.H.						
806	16000	FIELD OFFICE, TYPE A	12	MONTH						
624	10000	MOBILIZATION	LUMP							

O.B.T. = AMERITECH ( FORMERLY OHIO BELL TELEPHONE )  
E.O.G. = EAST OHIO GAS

NOTE: THE AREA OF STEEL LISTED FOR EACH BRIDGE REPRESENTS THE TOTAL SURFACE AREA OF STRUCTURAL STEEL TO BE COATED.

PLOTTED BY: nmc | loy  
 PLOTTED FROM: i:\user.s\mml\loy\lloyd\20055\estimate.dgn  
 FILENAME: dgn  
 PLOT SUBMITTED: 24-FEB-1999 14:29

OHIO DEPARTMENT OF TRANSPORTATION DISTRICT 12 BRIDGE DEPT.  
 ESTIMATED QUANTITIES  
 LAK-2-00.55 & VAR.  
 DATE: 10-94  
 REVIEWED: GWM  
 DRAWN: MPC  
 DESIGNED: MJM  
 CHECKED: BGT  
 STRUCTURE FILE NUMBER: VARIOUS  
 REVISION: DEL 3-96