thickness) shall be measured for payment.

Surface Preparation: This lump sum or m² (square feet) item includes all labor, materials and equipment necessary to: contain, collect, store, evaluate, ship, treat and dispose of all waste materials generated by this project and to prepare the surface as required by these specifications, prior to applying the prime coat.

815.16 BASIS OF PAYMENT. Payment for field painting will be made at the contract prices for: Item Unit Description

Hem	Unit	Description
815	Square meter (square foot),	Surface preparation of
	lump sum	existing steel, System OZEU
815	Square meter (square foot),	Field painting of existing steel,
	lump sum	prime coat, System OZEU
815	Square mete, (square foot),	Field Painting of existing steel,
	Lump sum	Intermediate coat, System OZEU
815	Square meter (square foot),	Field Painting of existing steel,
	Lump sum	Finish coat, System OZEU
815	Man Hour	Grinding Fins, Tears, Slivers
815	Meter (Linear foot)	Grinding Flange Edges
815	Meter (Linear foot)	Caulking

9