

SUMMARY

TABLES

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

11
57

LAKE COUNTY
LAK. - 2 - 1.80

QUANTITY CALCULATIONS
BY R.L.B. DATE 1/31/73
CHKD. K.N.M. DATE 2/2/73
F. A. THOMAS & ASSOC. INC.

DRIVEWAYS											
SHEET N ^o	LOCATION			EXIST. DRIVE TYPE	203	301	404	452	603	202	
					EXCAVATION	5" BIT. AGG. BASE	1" ASPH. CONC.	8" PLAIN PORTLAND CEMENT CONC. PAV'T.	TYPE "D" COND. 12"	PAVE-MENT REMOVAL	PIPE REMOVED 24" & UNDER
	STREET	STA.	SIDE L OR R		CU. YDS.	CU. YDS.	CU. YDS.	SQ. YDS.	LIN. FT.	SQ. YDS.	LIN. FT.
16	LAKELAND BLVD. (W)	1+99	LEFT	ASPH.	10.4	8.7	1.7		42		
16	LAKELAND BLVD. (W)	3+92	LEFT	ASPH.	10.7	8.9	1.8			38	
18	LAKELAND BLVD. (E)	0+77	RIGHT	ASPH.	6.9	5.7	1.1				
18	LAKELAND BLVD. (E)	1+73	RIGHT	ASPH.	11.3	9.4	1.9				
18	LAKELAND BLVD. (E)	3+24	RIGHT	CONC.				35.0		50.2	
14	FOREST GROVE	1+42	RIGHT	CONC.				15.2		15.2	
TOTAL					39.3	32.7	6.5	50.2	42	65.4	38

EARTH WORK SUMMARY							
SHEET N ^o	LOCATION	203		659			
		EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION		EMBANKMENT		SEEDING & MULCHING	
		CU.	YDS.	CU.	YDS.	SQ.	YDS.
32	FOREST GROVE	438		114		449	
24-25	RAMP N ^o 5	406		134		834	
26-27	RAMP N ^o 8	818		184		1499	
28-29	LAKELAND BLVD. (W)	225		28		449	
30-31	LAKELAND BLVD. (E)	350		28		505	
11	DRIVES	39					
TOTAL		2,276 CU. YDS.		488 CU. YDS.		3,736 SQ. YDS.	

LAKELAND FREEWAY & E. 305th ST. INTERCHANGE