

SUPERELEVATION TABLES

FED. RD. DIVISION	STATE	PROJECT
2	OHIO	LAKE COUNTY LAK-2-10.35

RAMP E

STATION	℄ ELEV.	OPPOSITE EDGE ELEV.	REMARKS
0+00	622.02	CONTROLLED BY S.R.2 PAVT. EDGE	SEE 1" = 20' SCALE DRAWINGS
0+25	622.07	"	
0+50	622.13	"	
0+72.82	622.16	"	BEGIN SUPERELEVATION
0+75	622.16	"	
1+00	622.10	"	
1+25	621.98	"	
1+50	621.83	"	
1+75	621.67	622.34	
2+00	621.48	622.28	
2+25	621.25	622.18	
2+42.82	621.12	622.16	
2+50	621.08	622.13	
2+75	620.97	621.92	
3+00	620.93	621.90	
3+25	620.96	621.94	
3+50	621.07	622.06	
3+75	621.25	622.26	
4+00	621.51	622.54	
4+17.89	621.74	622.78	END FULL SUPERELEVATION
4+25	621.85	622.86	
4+50	622.26	623.15	
4+75	622.75	623.51	
5+00	623.31	623.94	
5+25	623.95	624.44	
5+50	624.67	625.03	
5+75	625.45	625.68	
6+00	626.32	626.42	
6+17.89	626.98	626.98	LEVEL SECTION & SHIFTS 16' RT.
6+25	627.26	627.30	
6+50	628.28	628.45	
6+75	629.37	629.67	
7+00	630.53	630.97	
7+25	631.77	632.34	
7+50	633.02	633.72	
7+75	634.27	635.11	
8+00	635.52	636.49	
8+25	636.77	637.87	
8+50	638.02	639.26	
8+67.89	638.91	640.24	ATTAIN FULL SUPERELEVATION
8+75	639.27	640.60	
9+00	640.52	641.85	
9+25	641.77	643.10	
9+50	643.02	644.35	
9+75	644.27	645.60	
10+00	645.52	646.85	
10+25	646.77	648.10	
10+50	648.02	649.35	
10+75	649.27	650.60	
11+00	650.52	651.85	
11+25	651.77	653.10	
11+50	653.02	654.35	
11+75	654.27	655.60	
12+00	655.52	656.85	
12+25	656.77	658.10	
12+50	658.01	659.34	
12+75	659.19	660.52	
13+00	660.32	661.65	
13+25	661.38	662.71	
13+50	662.38	663.71	
13+75	663.33	664.66	
14+00	664.21	665.54	
14+25	665.03	666.36	
14+50	665.79	667.12	
14+75	666.49	667.82	
15+00	667.14	668.47	
15+25	667.72	669.05	
15+50	668.24	669.57	
15+75	668.70	670.03	
16+00	669.10	670.43	
16+25	669.44	670.77	
16+50	669.72	671.05	

RAMP E

STATION	℄ ELEV.	OPPOSITE EDGE ELEV.	REMARKS
16+75	669.94	671.27	
17+00	670.10	671.43	
17+25	670.20	671.53	
17+50	670.24	671.57	
17+75	670.22	671.55	
18+00	670.14	671.47	
18+25	669.99	671.32	
18+35.06	669.92	671.25	END FULL SUPERELEVATION
18+50	669.79	671.08	
18+75	669.53	670.74	
19+00	669.21	670.34	
19+25	668.83	669.88	
19+50	668.38	669.36	
19+75	667.88	668.78	
20+00	667.32	668.14	
20+25	666.69	667.44	
20+50	666.01	666.68	
20+75	665.27	665.86	
21+00	664.52	665.03	
21+25	663.77	664.21	
21+50	663.02	663.38	
21+75	662.27	662.55	
21+85.06	661.97	662.22	BEGIN NORMAL SECTION

RAMP G

STATION	℄ ELEV.	OPPOSITE EDGE ELEV.	REMARKS
31+25	647.11	648.44	
31+50	647.13	648.46	
31+75	647.11	648.44	
32+00	647.06	648.39	
32+25	646.97	648.30	
32+50	646.84	648.17	
32+75	646.68	648.01	
33+00	646.49	647.82	
33+25	646.26	647.59	
33+50	645.99	647.32	
33+75	645.68	647.01	
34+00	645.34	646.67	
34+25	644.97	646.30	
34+50	644.56	645.89	
34+75	644.11	645.44	
35+00	643.63	644.96	
35+25	643.13	644.46	
35+50	642.63	643.96	
35+75	642.13	643.46	
36+00	641.63	642.96	
36+25	641.13	642.46	
36+50	640.63	641.96	
36+75	640.13	641.46	
37+00	639.63	640.96	
37+25	639.13	640.46	
37+50	638.63	639.96	
37+75	638.13	639.46	
38+00	637.63	638.96	
38+25	637.13	638.46	
38+50	636.63	637.96	
38+54.73	636.54	637.87	END FULL SUPERELEVATION
38+75	636.13	637.37	
39+00	635.63	636.72	
39+25	635.13	636.09	
39+50	634.63	635.46	
39+75	634.13	634.82	
40+00	633.63	634.19	
40+25	633.13	633.56	
40+50	632.63	632.92	
40+75	632.13	632.29	
41+00	631.63	631.66	
41+04.73	631.54	631.54	LEVEL SECTION & SHIFTS 16' LT.
41+25	631.13	631.24	
41+50	630.63	630.87	
41+75	630.13	630.50	
42+00	629.63	630.14	
42+25	629.16	629.80	
42+50	628.77	629.54	
42+75	628.46	629.37	
43+00	628.22	629.22	
43+04.73	628.20	629.20	ATTAIN FULL SUPERELEVATION
43+25	628.05	629.11	
43+50	627.96	629.05	
43+54.54	627.96	629.06	END FULL SUPERELEVATION
43+75	627.95	628.98	
44+00	628.01	628.94	
44+25	628.14	628.96	
44+50	628.35	629.03	
44+75	628.59	629.14	
45+00	628.81	629.22	
45+24.54	628.98	629.26	BEGIN NORMAL SECTION
45+25	628.98	629.26	
45+50	629.09	629.37	
45+75	629.13	629.37	CONTROLLED BY S.R.2 PAVT. EDGE
46+00	629.15	"	SEE 1" = 20' SCALE DRAWINGS
46+25	629.16	"	
46+50	629.15	"	
46+75	629.13	"	
46+86.23	629.13	"	

RAMP G

STATION	℄ ELEV.	OPPOSITE EDGE ELEV.	REMARKS
22+35	634.94	635.18	BEGIN SUPERELEVATION
22+50	634.97	635.26	
22+75	635.05	635.42	
23+00	635.17	635.62	
23+25	635.33	635.86	
23+50	635.54	636.14	
23+75	635.78	636.46	
24+00	636.07	636.83	
24+25	636.40	637.24	
24+50	636.77	637.69	
24+75	637.18	638.17	
25+00	637.64	638.71	
25+25	638.13	639.28	
25+50	638.63	639.85	
25+75	639.13	640.43	
25+85	639.33	640.66	ATTAIN FULL SUPERELEVATION
26+00	639.63	640.96	
26+25	640.13	641.46	
26+50	640.63	641.96	
26+75	641.13	642.46	
27+00	641.63	642.96	
27+25	642.13	643.46	
27+50	642.63	643.96	
27+75	643.13	644.46	
28+00	643.63	644.96	
28+25	644.11	645.44	
28+50	644.56	645.89	
28+75	644.97	646.30	
29+00	645.34	646.67	
29+25	645.68	647.01	
29+50	645.99	647.32	
29+75	646.26	647.59	
30+00	646.49	647.82	
30+25	646.68	648.01	
30+50	646.84	648.17	
30+75	646.97	648.30	
31+00	647.06	648.39	