

# SUPERELEVATION TABLES

FED. RD. DIVISION	STATE	PROJECT
2	OHIO	

15  
384

P.I. STA. 723 + 82.77      RELOC. S. R. 2      SUPER. = 0.030'/FT.

STATION	46' LEFT	34' LEFT	22' LEFT & RIGHT	34' RIGHT	46' RIGHT
718+25	651.68	651.32	650.96	650.60	650.24
718+50	651.53	651.17	650.81	650.45	650.09
718+75	651.36	651.00	650.64	650.28	649.92
719+00	651.16	650.80	650.44	650.08	649.72
719+25	650.95	650.59	650.23	649.87	649.51
719+50	650.71	650.35	649.99	649.63	649.27
719+75	650.45	650.09	649.73	649.37	649.01
720+00	650.18	649.82	649.46	649.10	648.74
720+25	649.88	649.52	649.16	648.80	648.44
720+50	649.55	649.19	648.83	648.47	648.11
720+75	649.21	648.85	648.49	648.13	647.77
721+00	648.85	648.49	648.13	647.77	647.41
721+25	648.47	648.11	647.75	647.39	647.03
721+50	648.06	647.70	647.34	646.98	646.62
721+75	647.64	647.28	646.92	646.56	646.20
722+00	647.19	646.83	646.47	646.11	645.75
722+25	646.72	646.36	646.00	645.64	645.28
722+50	646.23	645.87	645.51	645.15	644.79
722+75	645.73	645.37	645.01	644.65	644.29
723+00	645.23	644.87	644.51	644.15	643.79
723+25	644.73	644.37	644.01	643.65	643.29
723+50	644.23	643.87	643.51	643.15	642.79
723+75	643.73	643.37	643.01	642.65	642.29
724+00	643.23	642.87	642.51	642.15	641.79
724+25	642.73	642.37	642.01	641.65	641.29
724+50	642.23	641.87	641.51	641.15	640.79
724+75	641.73	641.37	641.01	640.65	640.29
725+00	641.23	640.87	640.51	640.15	639.79
725+25	640.73	640.37	640.01	639.65	639.29
725+50	640.23	639.87	639.51	639.15	638.79
725+75	639.73	639.37	639.01	638.65	638.29
726+00	639.23	638.87	638.51	638.15	637.79
726+25	638.73	638.37	638.01	637.65	637.29
726+50	638.23	637.87	637.51	637.15	636.79
726+75	637.73	637.37	637.01	636.65	636.29
727+00	637.23	636.87	636.51	636.15	635.79
727+25	636.73	636.37	636.01	635.65	635.29
727+50	636.23	635.87	635.51	635.15	634.79
727+75	635.73	635.37	635.01	634.65	634.29
728+00	635.23	634.87	634.51	634.15	633.79
728+25	634.73	634.37	634.01	633.65	633.29
728+50	634.23	633.87	633.51	633.15	632.79
728+75	633.73	633.37	633.01	632.65	632.29
729+00	633.23	632.87	632.51	632.15	631.79
729+25	632.73	632.37	632.01	631.65	631.29
729+50	632.23	631.87	631.51	631.15	630.79
729+75	631.73	631.37	631.01	630.65	630.29
730+00	631.23	630.87	630.51	630.15	629.79
730+25	630.73	630.37	630.01	629.65	629.29
730+50	630.23	629.87	629.51	629.15	628.79
730+75	629.73	629.37	629.01	628.65	628.29
731+00	629.23	628.87	628.51	628.15	627.79
731+25	628.73	628.37	628.01	627.65	627.29
731+50	628.24	627.88	627.52	627.16	626.80
731+75	627.75	627.39	627.03	626.67	626.31
732+00	627.27	626.91	626.55	626.19	625.83
732+25	626.80	626.44	626.08	625.72	625.36
732+50	626.33	625.97	625.61	625.25	624.89
732+75	625.87	625.51	625.15	624.79	624.43
733+00	625.41	625.05	624.69	624.33	623.97
733+25	624.95	624.59	624.23	623.87	623.51
733+50	624.51	624.15	623.79	623.43	623.07
733+75	624.06	623.70	623.34	622.98	622.62
734+00	623.63	623.27	622.91	622.55	622.19
734+25	623.20	622.84	622.48	622.12	621.76
734+50	622.77	622.41	622.05	621.69	621.33
734+75	622.35	621.99	621.63	621.27	620.91
735+00	621.94	621.58	621.22	620.86	620.50

P.I. STA. 723 + 82.77      RELOC. S. R. 2      SUPER. = 0.030'/FT.

STATION	46' LEFT	34' LEFT	22' LEFT & RIGHT	34' RIGHT	46' RIGHT
735+25	621.53	621.17	620.81	620.45	620.09
735+50	621.12	620.76	620.40	620.04	619.68
735+75	620.73	620.37	620.01	619.65	619.29
736+00	620.33	619.97	619.61	619.25	618.89
736+25	619.95	619.59	619.23	618.87	618.51
736+50	619.56	619.20	618.84	618.48	618.12
736+75	619.19	618.83	618.47	618.11	617.75
737+00	618.82	618.46	618.10	617.74	617.38
737+25	618.45	618.09	617.73	617.37	617.01
737+50	618.09	617.73	617.37	617.01	616.65
737+75	617.74	617.38	617.02	616.66	616.30
738+00	617.39	617.03	616.67	616.31	615.95
738+25	617.05	616.69	616.33	615.97	615.61
738+50	616.71	616.35	615.99	615.63	615.27
738+75	616.38	616.02	615.66	615.30	614.94
739+00	616.05	615.69	615.33	614.97	614.61
739+25	615.73	615.37	615.01	614.65	614.29
739+50	615.42	615.06	614.70	614.34	613.98
739+75	615.11	614.75	614.39	614.03	613.67
740+00	614.80	614.44	614.08	613.72	613.36
740+25	614.51	614.15	613.79	613.43	613.07
740+35	614.39	614.03	613.67	613.31	612.95
740+50	614.14	613.82	613.49	613.16	612.84
740+75	613.74	613.48	613.21	612.94	612.68
740+90.64	613.48	613.26	613.03	612.80	612.58
740+97.02	613.37	613.16	612.95	612.74	612.53
741+00	613.33	613.13	612.92	612.71	612.51
741+06.27	613.23	613.04	612.85	612.66	612.47
741+25	612.94	612.84	612.65	612.55	612.36
741+45	612.61	612.61	612.42	612.42	612.23
741+50	612.55	612.56	612.37	612.38	612.19
741+75	612.22	612.30	612.11	612.19	612.00
742+00	611.90	612.04	611.85	611.99	611.80
742+20	611.64	611.83	611.64	611.83	611.64

LAKE COUNTY  
LAK-2-14.22