11-5

GENERAL SUMMARY

I CITY OF PAINESVILLE
II PAINESVILLE TOWNSHIP

CALC. BY	LAKE COUNTY	OHIO	70
DATE	LAK-2-14.38	FHWA REGION 5	138
CHKD. BY		FEDERAL PROJECT	
DATE			

ITEM	SHEET NUMBER 66 I	66 II	72 I	72 II	73 I	73 II	74 I	74 II	79 I	79 II	80 I	80 II	10 I	10 II	COST PARTICIPATION I	COST PARTICIPATION II	ITEM	QUANT.	UNIT	DESCRIPTION
																				TRAFFIC CONTROL
620	17	39													17	39	620	56	EACH	DELINEATOR REMOVED FOR DISPOSAL
620			122	92											122	92	620	214	EACH	DELINEATOR, TYPE C, FLEXIBLE POST MOUNTED
620			4	6											4	6	620	10	EACH	DELINEATOR, TYPE C, BRACKET MOUNTED
620			59	33											59	33	620	92	EACH	DELINEATOR, TYPE D, FLEXIBLE POST MOUNTED
620									6	4					6	4	620	10	EACH	REFLECTOR, TYPE D
													6800	5500	6800	5500	621	12300	LIN.FT.	REMOVAL OF PAVEMENT MARKINGS
621					10.32	10.17									10.32	10.17	621	20.49	MILE	EDGE LINES
847					4.33	4.51									4.33	4.51	847	8.84	MILE	LANE LINES, 947.02
847					1005	1844									1005	1844	847	2849	LIN.FT.	CHANNELIZING LINES, 947.02
847					68	50									68	50	847	118	LIN.FT.	STOP LINES, 947.02
847					152	2088									152	2088	847	2240	LIN.FT.	TRANSVERSE LINES, 947.02
847					8	4									8	4	847	12	EACH	LANE ARROWS, 947.02
847					4	2									4	2	847	6	EACH	WORD ONLY ON PAVEMENT, 72-IN. 947.02
847						0.70										0.70	847	0.70	MILE	8" EDGE LINE, 947.02
847					13										13		847	13	LIN.FT.	12" TRANSVERSE LINES, 947.02
625											6	5			6	5	625	11	EACH	GROUND ROD
630							48	53							48	53	630	101	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL
630							6	7							6	7	630	13	EACH	REMOVAL OF GROUND MOUNTED MAJOR SIGN AND DISPOSAL
630							23	42							23	42	630	65	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL
630							16	18							16	18	630	34	EACH	REMOVAL OF GROUND MOUNTED BEAM SUPPORT AND DISPOSAL
630								2								2	630	2	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION
630											5	12			5	12	630	17	EACH	REMOVAL OF OVERHEAD MOUNTED SIGN AND DISPOSAL
630											1				1		630	1	EACH	REMOVAL OF OVERHEAD SIGN SUPPORT AND DISPOSAL, TYPE 816 9.24, DES. 4
630											1				1		630	1	EACH	REMOVAL OF OVERHEAD SIGN SUPPORT AND DISPOSAL, TYPE 816 10.48, DES. 5
630												2				2	630	2	EACH	REMOVAL OF OVERHEAD SIGN SUPPORT AND DISPOSAL, TYPE 816 10.48 DES. 7
630											1				1		630	1	EACH	REMOVAL OF OVERHEAD SIGN SUPPORT AND DISPOSAL, TYPE 816 10.48 DES. 9
630											1				1		630	1	EACH	REMOVAL OF OVERHEAD MOUNTED SIGN AND REERECTION
630											1				1		630	1	EACH	REMOVAL OF OVERHEAD SIGN SUPPORT AND REERECTION, TYPE TC-12.30
630											23.02	38.95			23.02	38.95	630	62	CU.YD.	CONCRETE FOR ANCHOR BASE FOUNDATIONS
630									31.18	21.76					31.18	21.76	630	52.94	CU.YD.	CONCRETE FOR EMBEDDED FOUNDATIONS
630												1				1	630	1	EACH	EXISTING SIGN REVISED WITH DEMOUNTABLE COPY
630									677	579					677	579	630	1256	SQ.FT.	SIGNS, FLAT SHEET, TYPE G
630									1294	971	769	1700			2063	2671	630	4734	SQ.FT.	SIGNS, EXTRUSHEET, TYPE G
630												23				23	630	23	EACH	SIGN ATTACHMENT ASSEMBLY
630								2	1						1	2	630	3	EACH	SIGN SUPPORT ASSEMBLY, POLE MOUNTED
630									727	424					727	424	630	1151	LIN.FT.	GROUND-MOUNTED SUPPORTS, NO. 3 POST
630									405	625					405	625	630	1030	LIN.FT.	GROUND-MOUNTED SUPPORTS, NO. 4 POST
630										32						32	630	32	LIN.FT.	ONE WAY SUPPORTS, NO. 4 POST.
630									95	32					95	32	630	127	LIN.FT.	GROUND-MOUNTED SUPPORTS, S4 X 7.7 BEAM
630									66	74					66	74	630	140	LIN.FT.	GROUND-MOUNTED SUPPORTS, W6 X 9 BEAM
630									243	156					243	156	630	399	LIN.FT.	GROUND-MOUNTED SUPPORTS, W10 X 12 BEAM
630										187						187	630	187	LIN.FT.	GROUND-MOUNTED SUPPORTS, W8 X 18 BEAM
630																	630			
630									281	81					281	81	630	362	LIN.FT.	GROUND-MOUNTED SUPPORTS, W12 X 30 BEAM
630									22	15					22	15	630	37	EACH	BREAKAWAY BEAM CONNECTION
630												1				1	630	1	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-7.65, DESIGN 6, 50'-0" SPAN
630												1				1	630	1	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-7.65, DESIGN 6, 70'-0" SPAN
630											1				1		630	1	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-7.65, DESIGN 6, 72'-0" SPAN
630												1				1	630	1	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-7.65, DESIGN 8, 80'-0" SPAN
630											1				1		630	1	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-9.10, DESIGN 2, 9'-0" ARM
630												1				1	630	1	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-12.30, DESIGN 3, 16'-0" ARM
630											1				1		630	1	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-12.30, DESIGN 4, 25'-0" ARM
630											1				1		630	1	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-12.30, DESIGN 10 30'-0" ARM
630											1				1		630	1	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-16.20, DESIGN 3, 35'-0" ARM
											1	1			1	1	630	2	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-12.30 DESIGN 4, 20'-0" ARM