

TRAFFIC CONTROL QUANTITIES

LAKE COUNTY
LAK-2-14.38

OHIO
FHWA REGION 5
FEDERAL PROJECT

77
138

GROUND MOUNTED SIGNS

SIGN NO.	PLAN SHEET NO.	ELEVATION VIEW SHEET NO.	SPECIAL DETAIL SHEET NO.	LOCATION	SIGN CODE NO.	SIGN SIZE	630	630	630	630	630	630	630	630	630	630	630	630	630	630	620	630	630	630
							SIGNS, FLAT SHEET, TYPE G	SIGNS, EXTRUSHEET, TYPE G	GROUND MOUNTED SUPPORTS, NO. 3 POST	GROUND MOUNTED SUPPORTS, NO. 4 POST	ONE WAY SUPPORTS, NO. 4 POST	GROUND MOUNTED SUPPORTS, S4x 7.7 BEAM	GROUND MOUNTED SUPPORTS, W6x 9 BEAM	GROUND MOUNTED SUPPORTS, W10x 12 BEAM	GROUND MOUNTED SUPPORTS, W8x 18 BEAM	GROUND MOUNTED SUPPORTS, W10x 22 BEAM	GROUND MOUNTED SUPPORTS, W12x 30 BEAM	REFLECTOR, TYPE D	CONCRETE FOR EMBEDDED FOUNDATIONS	BREAKAWAY BEAM CONNECTION				
							SO FT	SO FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	EACH		CU FT	EACH	
155	83			(D)CITY OF PAINESVILLE S.R. 283 2 + 00 RT.	M-40-24	24' x 12'	2.0		13.5															
					M-2-24-3	30' x 24'	5.0																	
156	83			3 + 00 LT.	M-17-24	24' x 12'	2.0		14.5															
					M-2-24-3	30' x 24'	5.0																	
					M-21-21	21' x 15'	2.19																	
157	83			3 + 00 LT.	M-2-24-3	30' x 24'	5.0		13.5															
					M-19-21	21' x 15'	2.19																	
158	83			3 + 00 LT.	M-8-24	24' x 12'	2.0		14.5															
					M-2-24-2	24' x 24'	4.0																	
					M-19-21	21' x 15'	2.19																	
159	82		66	S.R. 2 686 + 70 LT.	W-49R-48	48' x 48'	16.0			14.0-14.0														
160	84		66	690 + 00 RT.	W-49R-48	48' x 48'	16.0			14.0-14.0														
161	84	93	66	691 + 82 LT.	GF-72	72' x 60'		30.0				16.0-16.0										0.54	2	
162	84			694 + 49 LT.	W-97-48	48' x 60'	20.0			15.5-16.0														
163	84			698 + 19 RT.	X-6L	12' x 36'	3.0		10															
164	84			698 + 62 RT.	X-6R	12' x 36'	3.0		10															
165	84			699 + 59 LT.	X-6R	12' x 36'	3.0		10															
166	84			699 + 92 LT.	X-6L	12' x 36'	3.0		10															
167	84			704 + 00 RT.	M-39-36	36' x 18'	4.5			15.0-16.0														
					M-2-36-2	36' x 36'	9.0																	
168	84			713 + 63 RT.	X-6L	12' x 36'	3.0		10															
169	84			713 + 66 RT.	X-6R	12' x 36'	3.0		10															
170	84			715 + 20 LT.	X-6R	12' x 36'	3.0		10															
171	84			715 + 23 LT.	X-6L	12' x 36'	3.0		10															
172	84			715 + 30 RT.	R-10-48	48' x 60'	20.0			16.0-17.5														
173	85			717 + 60 RT.	X-6L	12' x 36'	3.0		10															
174	85			717 + 64 RT.	X-6R	12' x 36'	3.0		10															
175	85			719 + 16 LT.	X-6R	12' x 36'	3.0		10															
176	85			719 + 21 LT.	X-6L	12' x 36'	3.0		10															
177	85	94		720 + 15 LT.	GB	240' x 144'		240.0									(28.5-32.75-37.0)					4.50		
178	85	93		723 + 00 RT.	GJ	180' x 60'		75.0				19.0-23.5										2.20		
179	85			730 + 83 CT.	R-123-36	36' x 36'	9.0			15														
					R-19-24	24' x 30'	5.0																	
180	85			731 + 17 CT.	R-123-36	36' x 36'	9.0			15														
					R-19-24	24' x 30'	5.0																	
181	85	93		733 + 35 LT.	GB	168' x 60'		40.0				19.0-20.75										2.20	2	
182	85	96		740 + 90 LT.	GSH	120' x 48'		70.0				17.0-18.0												
183	86	94		749 + 50 LT.	GB	240' x 144'		240.0									(26.0-30.0-34.0)					4.50	3	
184	86	95		762 + 20 RT.	GB	264' x 144'		264.0									(26.5-30.75-35)					4.50	3	
185	86			768 + 90 CT.	R-123-36	36' x 36'	9.0			15														
					R-19-24	24' x 30'	5.0																	
186	86			769 + 27 CT.	R-123-36	36' x 36'	9.0			15														
					R-19-24	24' x 36'	5.0																	
SHEET SUB-TOTALS																								
I. CITY OF PAINESVILLE							209.07	959.0	176	212.0			32.0	35.0	82.25			280.5			4		20.64	10

TRAFFIC CONTROL QUANTITIES, GROUND MOUNTED SIGNS