

TRAFFIC CONTROL QUANTITIES

LAKE COUNTY
LAK-2-14.38

OHIO
FHWA REGION 5
FEDERAL PROJECT

79
138

GROUND MOUNTED SIGNS

SIGN NO.	PLAN SHEET NO.	ELEVATION VIEW SHEET NO.	SPECIAL DETAIL SHEET NO.	LOCATION	SIGN CODE NO.	SIGN SIZE	630	630	630	630	630	630	630	630	630	630	630	630	630	620	630	630	630	630	
							SIGNS, FLAT SHEET, TYPE G	SIGNS, EXTRUSHEET, TYPE G	GROUND MOUNTED SUPPORTS, NO. 3 POST	GROUND MOUNTED SUPPORTS, NO. 4 POST	ONE WAY SUPPORTS, NO. 4 POST	GROUND MOUNTED SUPPORTS, S4x 7.7 BEAM	GROUND MOUNTED SUPPORTS, W6x 9 BEAM	GROUND MOUNTED SUPPORTS, W10x 12 BEAM	GROUND MOUNTED SUPPORTS, W8x 18 BEAM	GROUND MOUNTED SUPPORTS, W10x 22 BEAM	GROUND MOUNTED SUPPORTS, W12x 30 BEAM	SIGN SUPPORT ASSEMBLY, POLE MOUNTED	REFLECTOR, TYPE D	CONCRETE FOR EMBEDDED FOUNDATIONS	BREAKAWAY BEAM CONNECTION				
							SO FT	SO FT	LIN FT	LIN FT		LIN FT	LIN FT	LIN FT	LIN FT	LIN FT.	LIN FT.		EACH			CU FT	EACH		
II) PAINESVILLE TOWNSHIP																									
213	88			RAMP G 19 + 54 LT.	R-2-48	48"x48"x48"	6.93		14-14																
214	88			20 + 25 LT.	R-15D	30" x 30"	6.25		12																
215	88			RMP. G SPUR 20+20 LT.	R-15D	30" x 30"	6.25		12																
216	89	97		S.R. 2 837 + 50 RT.	GC	132" x 84"		77.0							24.5-25.0							2.20	2		
217	89			850 + 40 RT.	X-6R	12" x 36"	3.0		10																
218	89			850 + 90 RT.	X-6L	12" x 36"	3.0		10																
219	89			852 + 82 LT.	X-6L	12" x 36"	3.0		10																
220	89			853 + 29 LT.	X-6R	12" x 36"	3.0		10																
221	89	97		854 + 00 LT.	GJ	180" x 60"		75.0							200-24.5							2.20			
222	90			860 + 30 CT.	R-123-36	36" x 36"	9.0		15																
					R-19-24	24" x 30"	5.0																		
223	90			860 + 70 CT.	R-123-36	36" x 36"	9.0		15																
					R-19-24	24" x 30"	5.0																		
224	90	97		864 + 00 RT.	W-54B-192	192" x 60"		80.0							23.0-25.0							2.20	2		
225	90			866 + 25 LT.	M-40-36	36" x 18"	4.5		15.0-16.0																
					M-2-36-2	36" x 36"	9.0																		
226	90	97		877 + 13 RT.	W-54A-192	192" x 60"		80.0							16.0-19.0							2.20	2		
227	90	96		877 + 13 LT.	W-54A-192	192" x 60"		80.0							18.0-19.0							2.20	2		
228	90		66	879 + 00 RT.	W-2-36	36" x 36"	9.0		16.0																
					W-143-24	24" x 24"	4.0																		
229	91			881 + 50 LT.	R-10-48	48" x 60"	20.0		15.0-15.5																
230	91	96		885 + 00 RT.	W-32-96	96" x 48"		32.0							16.5-18.5							0.66	2		
231	91			887 + 00 LT.	R-15D	30" x 30"	6.25		12																
232	91		66	886 + 00 RT.	W-33-36	36" x 48"	12.0		14.0-14.5																
233	91		66	887 + 00 RT.	W-33-36	36" x 48"	12.0		14.0-14.5																
234	91		66	888 + 00 RT.	W-33-36	36" x 48"	12.0		14.0-14.5																
235	91		66	889 + 00 RT.	W-33-36	36" x 48"	12.0		14.0-14.5																
236	91			892 + 00 RT.	R-11A-48	48" x 60"	20.0		15.0-15.5																
237	91			U.S. 20 97 + 50 LT.	M-40-30	30" x 15"	3.13		14																
					M-1-30-2	30" x 30"	6.25																		
238	91			107 + 00 RT.	W-50R-48	48" x 48"	16.0		14.0-14.5																
239	91			113 + 25 RT.	R-10-48	48" x 60"	20.0		15.0-15.5																
240	91			117 + 10 RT.	M-39-30	30" x 15"	3.13		14																
					M-1-30-2	30" x 30"	6.25																		
241	91			118 + 50 CT.	R-38R-36	36" x 48"	12.0		14 - 14																
242	91			121 + 00 LT.	R-10-36	36" x 48"	12.0		14 - 14																
243	82		(I)	RAMP E 16 + 25 LT.	R-41A-36	36" x 24"	6.0		13																
244	82			16 + 25 RT.	R-41A-36	36" x 24"	6.0		13																
245	82			14 + 25 LT.	N-29-24	24" x 24"	4.0		13																
					N-15-24	24" x 6"	1.0																		
246	82		(I)	RAMP D 18 + 00 LT.	R-41A-36	36" x 24"	6.0		13																
					N-29-24	24" x 24"	4.0																		
					N-15-24	24" x 6"	1.0																		
247	82		(I)	RAMP D 18 + 00 RT.	R-41A-36	36" x 24"	6.0		13																
248	90	96	(II)	S.R. 2 864 + 00 CT.	W-54B-192	192" x 60"		80.0							200-20.5										
SHEET SUB-TOTALS																									
I CITY OF PAINESVILLE							34		65																
II PAINESVILLE TOWNSHIP							258.94	504	274	225		35.0	112.5	142.0					2			11.66	10		
TOTALS							677.25	1294.25	727	404.5		95.0	66	242.75		280.5		1		6		31.18	22		
							578.5	970.5	423.5	624.5		32.0	32.0	74	156.5	186.5		81.0		4		21.76	15		