LAKE COUNTY LAK-2-17.35 OHIO

REGION O

PLAN NO. BR-25-87

FEDERAL PROJECT

ESTIMATED QUANTITIES

BRIDGE LAK-2-1735 L&R			
ITEM	TOTAL	UNIT	DESCRIPTION
			ROADWAY
000	CLIMP	LUMP	PORTIONS OF STRUCTURE REMOVED
202 605	LUMP 160	L.F.	AGGREGATE DRAIN
SPECIAL	144	L.F.	PRESSURE RELIEF JOINT, TYPE C
			STRUCTURE
503	LUMP	LUMP	COFFERDAMS, CRIBS, AND SHEETING
509	3202	LBS.	REINFORCING STEEL, GRADE 60
510	107	EACH	DOWEL HOLES, AS PER PLAN
511	26	C.Y.	CLASS C CONCRETE, SUBSTRUCTURE, AS PER PLAN
SPECIAL	19	EACH	OVERHEAD DOWEL GROUTING SYSTEM
SPECIAL	32	L.F.	JOINT SEAL (8" X 4 " BITUMEN IMPREGNATED FOAM)
SPECIAL	32	L.F.	JOINT SEAL (4" X 2 " BITUMEN IMPREGNATED FOAM)
SPECIAL	5	EACH	WEEP HOLE EXTENSION
SPECIAL	48	L.F.	EPOXY INJECTION (SEE PROPOSAL NOTE)
SPECIAL	64	L.F.	POURED POLYURETHANE JOINT SEAL
			MAINTENANCE OF TRAFFIC
614	LUMP	LUMP	MAINTAINING TRAFFIC
		4	
			GENERAL
624	LUMP	LUMP	MOBILIZATION
		-	

STATE OF OHIO

DEPARTMENT OF TRANSPORTATION

DISTRICT 12 BRIDGE DEPARTMENT

ESTIMATED QUANITIES

BRIDGE Nº LAK-2-1735 L & R

S.R. 2 OVER RED CREEK

DESIGNED DRAWN TRACED CHECKED REVIEWED DATE REVISED B.M. T. K.R.D. K.Z.D. D.W.L. W.W.M.

6/87 6/87 6/87 6/20/87 6/20/87