REF. NO.	LOCATION				SHEET NO.	202				606							607	609	622									
	STATION		ROAD	SIDE		CURB REMOVED	GUARDRAIL REMOVED	FENCE REMOVED	CONCRETE BARRIER REMOVED	GUARDRAIL, TYPE 5	ANCHOR ASSEMBLY, TYPE B-98	ANCHOR ASSEMBLY, TYPE E-98	ANCHOR ASSEMBLY, TYPE T	BRIDGE TERMINAL ASSEMBLY, TYPE 1	BRIDGE TERMINAL ASSEMBLY, TYPE 2	IMPACT ATTENUATOR, TYPE 2-98 (UNIDIRECTIONAL)	FENCE, TYPE CLT	CURB, TYPE 6	BARRIER TRANSITION	CONCRETE BARRIER END SECTION, TYPE B	CONCRETE BARRIER, SINGLE SLOPE, TYPE B, AS PER PLAN	CONCRETE BARRIER, SINGLE SLOPE, TYPE B1	CONCRETE BARRIER, SINGLE SLOPE, TYPE D	CONCRETE BARRIER END ANCHOR, REINFORCED	CONCRETE BARRIER END SECTION, TYPE D	CONCRETE BARRIER END ANCHOR, REINFORCED, TYPE D	CONCRETE BARRIER END ANCHOR, REINFORCED, TYPE B1	
	FROM	TO																										
						FT	FT	FT	FT	FT	EACH	EACH	EACH	EACH	EACH	EACH	FT	FT	EA	EA	FT	FT	FT	EA	EA	EA	EA	
F-1	492+50	498+19	SR 2	LT	296												596											
F-2	492+50	495+97	SR 2	RT	296												360											
F-3	496+20	501+43	SR 2	RT	296												602											
F-4	498+41	501+44	SR 2	LT	296												380											
F-5	502+21	505+00	SR 2	RT	296												329											
F-6	501+21	505+00	SR 2	LT	296												349											
B-1	492+50	501+27	SR 2	CL	296																	812		1				
B-2	502+36	505+00	SR 2	CL	296																	229		1				
B-3	492+50	501+27	SR 2	LT	296																		822			1		
G-1	498+95	501+31	SR 2	RT	296					150		1		1														
G-2	502+32	502+84	SR 2	RT	296					12.5			1		1													
G-3	502+32	504+67	SR 2	LT	296					150		1		1														
R-1	505+00	514+50	SR 2	LT	297			950																				
R-2	505+00	514+50	SR 2	RT	297			950																				
F-1	505+00	514+50	SR 2	LT	297												950											
F-2	505+00	514+50	SR 2	RT	297												950											
B-1	505+00	510+00	SR 2	CL	297																	450						1
G-1	509+26	511+26	SR 2	LT	297					137.5		1	1															
G-2	510+00		SR 2	CL	297											1												
THIS SHEET TOTAL						0	0	1600	0	450	0	3	2	2	1	1	3620	0	0	0	0	0	1491	822	2	1	0	1	
SHEET 248 TOTAL						423	6025	6594	5335	1418.75	0	1	1	1	1	0	4063	30	3	0	0	0	1039	856	3	1	1	0	
SHEET 249 TOTAL						371	10484	4204	4553	2893.75	1	3	3	4	3	1	6479	0	0	0	0	737	3060	296	13	1	1	0	
SHEET 250 TOTAL						0	0	4642	5000	1162.5	1	1	0	2	0	0	3709	0	0	0	0	0	2210	1790	9	1	13	0	
SHEET 251 TOTAL						207	6241	3825	6720	2012.5	0	0	0	1	1	1	4731	2039	0	1	53	2022	2689	10	0	6	0	
SHEET 252 TOTAL						201	685	5697	7500	2368.75	5	2	8	2	3	0	6218	0	0	0	1452	4293	35	27	0	1	0	
SHEET 253 TOTAL						392	1026	5721	7500	662.5	1	1	2	0	0	1	2748	0	0	0	0	3460	0	10	0	0	0	
SHEET 254 TOTAL						399	3562	5809	3197	0	0	0	0	0	0	0	3292	0	0	0	0	2240	432	8	0	2	0	
GRAND TOTAL (CARRIED TO GENERAL SUMMARY)						1993	22623	38092	39805	10969	8	11	16	12	9	4	34880	2069	3	1	2242	19815	7020	82	4	24	1	

CALCULATED MDB
CHECKED PSB

ROADWAY SUBSUMMARY - S.R. 2

LAK-2-3.32

255
1679

G:\Project\lak\13486\roadway\sheets\13486GS008.dgn 11/26/2008 9:41:27 AM PBerdis