

g:\project\lak\13486\roadway\sheets\13486GS301.dgn 6/30/2008 10:47:44 AM dshoner

REF. NO.	STATION TO STATION		ROAD	SIDE	SHEET NO.	202	202	448	606	606	606	607	609
						GUARDRAIL REMOVED FT	FENCE REMOVED FT	3" ASPHALT CONCRETE, INTERMEDIATE COURSE, TYPE 1, PG64-22, UNDER GUARDRAIL, AS PER PLAN (3.5' WIDE) CU YD	GUARDRAIL, TYPE 5 FT	ANCHOR ASSEMBLY, TYPE E-98 EACH	BRIDGE TERMINAL ASSEMBLY, TYPE 1 EACH	FENCE, TYPE CLT FT	6" CONCRETE TRAFFIC ISLAND CU YD
R-1	88+00	96+45	RAMP A	RT	512								
F-1	87+97	96+45	RAMP A	RT	512		845					848	
C-1	89+28	91+00	RAMP A/E										15
R-1	90+80	95+17	RAMP B	RT	526		437						
F-1	90+80	95+17	RAMP B	RT	526							437	
R-1	80+25	86+00	RAMP D	RT	532	350							
F-1	83+74	86+00	RAMP D	LT	532							226	
G-1		86+00	RAMP D	LT	532			7.3	225		1		
G-2	83+59	84+75	RAMP D	RT	532			3.6	113	1	1		
R-1	86+00	94+10	RAMP D	LT	533	765							
F-1	86+00	92+73	RAMP D	LT	533							673	
G-1	86+00	93+37	RAMP D	LT	533			23.9	738	1			
R-1	201+81	207+14	RAMP BF	RT	556		533						
F-1	201+12	207+14	RAMP BF	RT	556							602	
C-1	200+75	206+88	RAMP BF	CL	556								37
TOTALS CARRIED TO GENERAL SUMMARY						1,115	1,815	35	1,075	2	2	2,786	52

CALCULATED
MDB
CHECKED
PSB

ROADWAY SUBSUMMARY - LOST NATION ROAD RAMPS

LAK - 2 - 3.32