REF. NO.	SHEET NO.	STATION FROM	STATION TO	SIDE	202 PAVEMENT REMOVED SQ YD	202 WALK REMOVED SQ FT	202 PIPE REMOVED, 24" AND UNDER FT	202 CATCH BASIN REMOVED EACH	601 PAYED GUTTER, TYPE 1-6 FT	603 6" CONDUIT, TYPE F FT	603 12" CONDUIT, TYPE B FT	603 15" CONDUIT, TYPE C FT	604 CATCH BASIN, NO. 3 EACH	604 CATCH BASIN, NO. 3A EACH	604 MANHOLE ADJUSTED TO GRADE EACH	604 MANHOLE RECONSTRUCTED TO GRADE EACH	605 6" BASE PIPE UNDERDRAIN WITH FABRIC WRAP FT	608 4" CONCRETE WALK SQ FT	609 CURB, TYPE 2-A FT
R1	654	124+00	126+66.05	LT	21														
R2	654	124+00	124+49.91	LT		255													
R3	654	124+00	124+08.65	RT	4														
R4	654	126+56.19	129+00	LT	309														
R5	654	126+42.96	129+00	LT		1289													
R6	654	126+91.15	129+00	RT	333														
R7	654	125+72	127+06	RT		877													
R8	654	127+44	129+00	RT		1324													
R9	654	124+00	129+00	RT/LT	509														
R10	654	125+30.97	125+62.72	LT		459													
R11	654	124+60.45	124+92.20	RT		455													
RD1	654	127+29		RT				1											
RD2	654	128+83	129+00	RT			22	1											
RD3	654	128+83		LT			36	2											
PG1	654	124+30.27	124+69.17	LT					39										
PG2	654	125+56.30	125+92.84	RT					37										
PG3	654	126+56.19	127+00	LT					44										
D1	654	128+82		LT							6	30	1						
D2	654	128+82	128+94	LT							12			1					
D3	654	128+82	128+94	RT							4		1						
D4	654	128+94	129+00	RT							18			1					
AJ1	654	127+32		LT												1			
AJ2	654	126+72		RT											1				
AJ3	654	128+83		LT												1			
W1	654	124+00	124+49.91	LT														834	
W2	654	124+60.45	124+92.20	RT														455	
W3	654	125+30.97	125+62.72	LT														459	
W4	654	126+42.96	129+00	LT														1813	
W5	654	125+72	129+00	RT														3169	
C1	654	124+00	124+66.05	LT													66		66
C2	654	124+00	124+08.65	RT													9		9
C3	654	126+56.19	129+00	LT													253		273
C4	654	126+91.15	129+00	RT						20							189		209
										20									
TOTALS CARRIED TO VINE ST. SUB-SUMMARIES					1176	4659	58	4	120	40	40	30	2	2	1	2	517	6730	557

CALCULATED EMF
CHECKED ABS

ESTIMATED QUANTITIES - VINE STREET (S.R. 640)
STA. 124+00.00 TO STA. 129+00.00

LAK-2-3.32

656
1679

J:\LAK\13486\roadway\sheets\13486GQ403.dgn 03-JUL-2008 1:57PM lintn