REF. NO.	LOCATION: STATION FROM	LOCATION: STATION TO	LOCATION: ROAD	LOCATION: SIDE	LOCATION: SHEET NO.	202 CATCH BASIN REMOVED	202 PIPE REMOVED 24" AND UNDER	202 HEADWALL REMOVED	601 ROCK CHANNEL PROTECTION, TYPE C WITH FABRIC FILTER		602 CONCRETE MASONRY	603 12" CONDUIT, TYPE B		603 12" CONDUIT, TYPE C	603 12" CONDUIT, TYPE F	603 15" CONDUIT, TYPE B				603 24" CONDUIT, TYPE B	603 24" CONDUIT, TYPE C		603 22"x34" CONDUIT, TYPE B	603 36" CONDUIT, TYPE B	604 CATCH BASIN NO. 2-2B W/ SOLID LID	604 CATCH BASIN NO. 3	604 CATCH BASIN NO. 3A	604 CATCH BASIN NO. 2-2B		604 CATCH BASIN NO. 5	604 MANHOLE NO. 3		604 MANHOLE ADJUSTED TO GRADE	604 CATCH BASIN RECONSTRUCTED TO GRADE W/MH CASTING				670
						EACH	FOOT	EACH	CU.YD.		CU.YD.	FOOT		FOOT	FOOT	FOOT				FOOT	FOOT		FOOT	FOOT	EACH	EACH	EACH	EACH		EACH	EACH		EACH	EACH				
RD-1	95+31.7	96+13.2	RAMP A	LT/RT	512	1	140																																
RD-2	93+13.2	95+31.7	RAMP A	RT	512	1	233	1																															
D-1	94+00.0	94+20.2	RAMP A/E	LT/RT	512											174														1	1								
D-2	92+75.7	94+20.2	RAMP A/E	LT	512						0.43									151																			
D-3	94+20.2	95+30.0	RAMP A/E	LT	512																135									1	1								
RD-1	92+63	92+90	RAMP B	LT/RT	526	1	155																																
D-1	92+63.8		RAMP B	LT/RT	526						0.25					174														1									
RC-1	92+63.8		RAMP B	LT	526				1.33																														
D-1	85+00.0	85+88.25	RAMP D	LT/RT	532											191														1	1								
D-2	83+43.5	85+00.0	RAMP D	RT	532						0.49										148																		
D-3	85+00.0	85+27.00	RAMP D	RT	532						0.43										26																		
D-1	206+75.0		RAMP B/F	RT	556						0.25					72										1													
D-2	205+50.0		RAMP B/F	RT	556						0.25					77										1													
D-3	204+25.0		RAMP B/F	RT	556						0.25					71										1													
D-4	203+01.5		RAMP B/F	LT/RT	556											3									1														
D-5	203+01.5		RAMP B/F	RT	556						0.25					90									1														
D-6	201+25.0		RAMP B/F	LT/RT	556											3										1													
D-7	201+25.0		RAMP B/F	RT	556						0.25					100										1													
RC-1	206+75.0		RAMP B/F	RT	556				1.33																														
RC-2	205+50.0		RAMP B/F	RT	556				1.33																														
RC-3	204+25.0		RAMP B/F	RT	556				1.33																														
RC-4	203+01.5		RAMP B/F	RT	556				1.33																														
RC-5	201+25.0		RAMP B/F	RT	556				1.33																														
D-1	114+79.9		ST. CLAIR	LT/RT	713							40														2													
D-2	114+79.9		ST. CLAIR	RT	713						0.25			20																									
RC-1	114+79.9		ST. CLAIR	RT	713				1.33																														
D-1	1+56.0		RIVERSIDE E	LT/RT	717							28														2													
D-2	1+56.0	1+58	RIVERSIDE E	LT	717									47												1													
D-3	1+58		RIVERSIDE W	RT	717							7																			1								
D-4	1+58		RIVERSIDE W	LT/RT	717							21														1													
SHEET TOTAL						3	528	1	9.31		3.10	96		71		955				151	309				2	11	2		4	4								

CALCULATED AGH
CHECKED PSB

DRAINAGE SUBSUMMARY

LAK-2-3.32

848/1679

G:\Project\lak\13486\drainage\sheets\13486DS404.dgn 6/25/2008 1:16:17 PM pberdis