SHEET NO.	PANEL BAY ID.	POST NUMBER	NOISE BARRIER POST STATION	NOISE BARRIER POST STATION & OFFSET (FT) (MAINLINE)	PROPOSED FINISHED GROUND ELEVATION	TOP OF DRILLED SHAFT ELEVATION	DRILLED SHAFT DEPTH (FT)	BOTTOM OF BARRIER ELEVATION	TOP OF BARRIER ELEVATION	BARRIER HEIGHT (FT)	606 NOISE BARRIER (ABSORPTIVE), OVER 10' TO 14' HEIGHT	606 NOISE BARRIER, MISC.: CONCRETE NOISE BARRIER POST AND DRILLED SHAFT FOUNDATION
											SQ FT	EACH
1028	D131							638.65	652.65	14.00	224	
		132	3020+96.00	492+36.79 63.92 LT	637.49	638.36	12.5					1
1028	D132							638.65	652.65	14.00	224	
		133	3021+12.00	492+52.79 63.92 LT	637.51	638.36	12.5					1
1028	D133							638.65	652.65	14.00	224	
		134	3021+28.00	492+68.79 63.92 LT	637.54	638.36	12.5					1
1028	D134							638.65	652.65	14.00	224	
		135	3021+44.00	492+84.79 63.92 LT	637.57	638.36	12.5					1
1028	D135							638.65	652.65	14.00	224	
		136	3021+60.00	493+00.79 63.92 LT	637.61	638.36	12.5					1
1028	D136							638.65	652.65	14.00	224	
		137	3021+76.00	493+16.79 63.92 LT	637.65	638.36	12.5					1
1028	D137							638.65	652.65	14.00	224	
		138	3021+92.00	493+32.79 63.92 LT	637.69	638.36	12.5					1
1028	D138							638.65	652.65	14.00	224	
		139	3022+08.00	493+48.79 63.92 LT	637.75	638.36	12.5					1
1028	D139							638.65	652.65	14.00	224	
		140	3022+24.00	493+64.79 63.92 LT	637.80	638.36	12.5					1
1028	D140							638.65	652.65	14.00	224	
		141	3022+40.00	493+80.79 63.92 LT	637.86	638.36	12.5					1
1028	D141							638.65	652.65	14.00	224	
		142	3022+56.00	493+96.79 63.92 LT	637.92	638.36	12.5					1
1028	D142							638.65	652.65	14.00	224	
		143	3022+72.00	494+12.79 63.92 LT	637.99	638.36	12.5					1
1028	D143							638.65	652.65	14.00	224	
		144	3022+88.00	494+28.79 63.92 LT	638.06	638.36	12.5					1
1028	D144							638.65	652.65	14.00	224	
		145	3023+04.00	494+44.79 63.92 LT	638.12	638.36	12.5					1
1028	D145							638.65	652.65	14.00	224	
		146	3023+20.00	494+60.79 63.92 LT	638.19	638.36	12.5					1
1028	D146							638.65	652.65	14.00	224	
		147	3023+36.00	494+76.79 63.92 LT	638.26	638.36	12.5					1
1028	D147							638.65	652.65	14.00	224	
		148	3023+52.00	494+92.79 63.92 LT	638.33	638.36	12.5					1
1028	D148							638.65	652.65	14.00	224	
		149	3023+68.00	495+08.79 63.92 LT	638.39	638.36	12.5					1
1028	D149							638.65	652.65	14.00	224	
		150	3023+84.00	495+24.79 63.92 LT	638.46	638.36	12.5					1
1028	D150							638.65	652.65	14.00	224	
		151	3024+00.00	495+40.79 63.92 LT	638.53	638.36	12.5					1
1028	D151							638.65	652.65	14.00	224	
		152	3024+16.00	495+56.79 63.92 LT	638.59	638.36	12.0					1
1028	D152							639.65	653.65	14.00	224	
		153	3024+32.00	495+72.79 63.92 LT	638.66	639.36	12.0					1
1028	D153							639.65	653.65	14.00	224	
		154	3024+48.00	495+88.79 63.92 LT	638.73	639.36	12.0					1
1028	D154							639.65	653.65	14.00	224	
		155	3024+64.00	496+04.79 63.92 LT	638.80	639.36	12.0					1
1028	D155							639.65	653.65	14.00	224	
		156	3024+80.00	496+20.79 63.92 LT	638.86	639.36	12.0					1
1028	D156							639.65	653.65	14.00	224	
		157	3024+96.00	496+36.79 63.92 LT	638.93	639.36	12.0					1
TOTALS CARRIED TO GENERAL SUMMARY											5824	26

CALCULATED DJP
CHECKED GGN

NOISE BARRIER SCHEDULE AND QUANTITIES
NOISE BARRIER D

LAK-2-3.32

1003
1679

\\Akron01\Data\Civil\2004108\00\13486\structures\noisebarrier\sheets\13486NPD12.dgn 6/16/2008 3:42:08 PM mmcellendick