SHEET NO.	REFERENCE NO.	LOCATION	STATION FROM	STATION TO	SIDE	646 EDGE LINE (WHITE), AS PER PLAN	646 EDGE LINE (YELLOW), AS PER PLAN	646 LANE LINE, AS PER PLAN	646 CENTER LINE - DOUBLE SOLID, AS PER PLAN	646 CENTER LINE - SOLID/BROKEN, AS PER PLAN	646 CHANNELIZING LINE, AS PER PLAN	646 STOP LINE, AS PER PLAN	646 CROSSWALK LINE, AS PER PLAN	646 TRANSVERSE LINE (WHITE), AS PER PLAN	646 TRANSVERSE LINE (YELLOW), AS PER PLAN	646 ISLAND MARKING, AS PER PLAN	642 BIKE SYMBOL MARKING, TYPE 1	646 LANE ARROW, AS PER PLAN	646 PAVEMENT MARKING, MISC.: WORD ON PAVEMENT, 44"	646 DOTTED LINE, AS PER PLAN		
						MILE	MILE	MILE	MILE	MILE	FT	FT	FT	FT	FT	SQ FT	EACH	EACH	EACH	FT		
1094	CH-1	SR 2	279+80	280+00	LT						20											
	CH-2		279+80	280+00	LT						20											
	CH-3		276+00	280+00	RT						400											
	CH-4		276+00	280+00	RT						400											
	EW-1		276+00	280+00	LT	0.08																
	EW-2		275+85	280+00	RT	0.08																
	EW-3		279+05	280+00	LT	0.02																
	EY-1		276+00	280+00	LT		0.08															
	EY-2		276+00	280+00	RT		0.08															
	EY-3		275+85	276+00	LT		0.01															
	EY-4		275+85	276+00	RT		0.01															
	LL-1		276+00	280+00	LT			0.08														
	LL-2		276+00	280+00	LT			0.08														
	LL-3		276+00	280+00	RT			0.08														
	LL-4		276+00	280+00	RT			0.08														
1095	CH-1	SR 2	280+00	282+64	LT						264											
	CH-2		280+00	282+64	LT						264											
	CH-3		280+00	284+40	RT						440											
	CH-4		280+00	283+40	RT						340											
	DL-1		282+64	292+50	LT															986		
	DL-2		284+40	292+50	RT															810		
	EW-1		280+00	292+50	LT	0.24																
	EW-2		280+00	292+50	RT	0.24																
	EY-1		280+00	292+50	LT		0.24															
	EY-2		280+00	292+50	RT		0.24															
	LL-1		280+00	292+50	LT			0.24														
	LL-2		280+00	292+50	LT			0.24														
	LL-3		280+00	292+50	RT			0.24														
	LL-4		280+00	292+50	RT			0.24														
1096	CH-1	SR 2	300+70	305+00	LT						430											
	CH-2		298+80	305+00	RT						620											
	CH-3		298+80	305+00	RT						620											
	DL-1		292+50	300+70	LT															820		
	DL-2		292+50	298+80	RT															630		
	EW-1		292+50	305+00	LT	0.24																
	EW-2		292+50	305+00	RT	0.24																
	EW-3		300+70	305+00	LT	0.09																
	EY-1		292+50	305+00	LT		0.24															
	EY-2		292+50	305+00	RT		0.24															
	LL-1		292+50	305+00	LT			0.24														
	LL-2		292+50	305+00	LT			0.24														
	LL-3		292+50	305+00	RT			0.24														
	LL-4		292+50	305+00	RT			0.24														
1097	CH-1	SR 2	305+00	310+80	RT						580											
	CH-2		305+00	310+90	RT						590											
	CH-3		305+00	309+58	RT						458											
	EW-1		305+00	317+00	LT	0.23																
	EW-2		305+00	317+50	LT	0.24																
	EW-3		305+00	317+00	RT	0.23																
	EW-4		305+00	317+50	RT	0.24																
TOTALS CARRIED TO SHEET				**1049**		2.17	1.14	2.24			5,446									3,246		

CALCULATED JMM
CHECKED DRJ

S.R. 2 PAVEMENT MARKING SUBSUMMARY

LAK-2-3.32

g:\project\lak\13486\traffic\sheets\13486TSPM001.dgn 6/23/2008 10:34:38 AM jmaderia