

SHEET NO.	REFERENCE NO.	LOCATION	STATION		SIDE	645	645	645	645					646	646	646	646	646	646	646	646	646	646	646
			EDGE LINE (WHITE), TYPE A	EDGE LINE (YELLOW), TYPE A		LANE LINE, TYPE A	CHANNELIZING LINE, TYPE A					EDGE LINE (WHITE), AS PER PLAN	EDGE LINE (YELLOW), AS PER PLAN	LANE LINE, AS PER PLAN	CENTER LINE - DOUBLE SOLID, AS PER PLAN	CENTER LINE - SOLID/BROKEN, AS PER PLAN	CHANNELIZING LINE, AS PER PLAN	STOP LINE, AS PER PLAN	CROSSWALK LINE, AS PER PLAN	TRANSVERSE/DIAGONAL LINE (WHITE), AS PER PLAN	TRANSVERSE/DIAGONAL LINE (YELLOW), AS PER PLAN	ISLAND MARKING, AS PER PLAN	LANE ARROW, AS PER PLAN	DOTTED LINE, 4", AS PER PLAN
			FROM	TO		MILE	MILE	MILE	FT					MILE	MILE	MILE	MILE	MILE	FT	FT	FT	FT	FT	FT
		SR 91																						
1125	EW-1		30+00	71+75	LT.									0.13										
	EW-2		30+00	82+40	RT.									0.12										
	EW-3		34+96	42+50	LT.									0.15										
	EY-1		30+00	33+77	LT.										0.08									
	EY-2		30+00	33+77	LT. & RT.										0.08									
	EY-3		34+96	42+50	LT.										0.15									
	LL-1		30+00	42+50	LT.											0.24								
	LL-2		30+00	33+73	RT.											0.08								
	CH-1		30+00	33+75	LT.												375							
	CH-2		31+18	33+73	RT.												255							
	CH-3		34+96	37+13	LT.												217							
	CH-4		34+96	36+08	LT.												112							
	SL-1		33+75		RT.														36					
	SL-2		34+94		LT.														48					
	SL-5		40+80		LT.														24					
	LA-1		30+20		LT.																		1	
	LA-2		30+86		LT.																		1	
	LA-3		31+52		LT.																		1	
	LA-4		32+18		LT.																		1	
	LA-5		32+84		LT.																		1	
	LA-6		33+50		LT.																		1	
	LA-7		31+65		RT.																		1	
	LA-8		32+31		RT.																		1	
	LA-9		32+97		RT.																		1	
	LA-10		33+63		RT.																		1	
	LA-11		35+06		LT.																		1	
	LA-12		35+72		LT.																		1	
	LA-13		36+38		LT.																		1	
	LA-14		37+04		LT.																		1	
	LA-15		35+06		LT.																		1	
	LA-16		35+72		LT.																		1	
		VOKES BLVD.																						
	CLS-1		71+75	74+17	LT.											0.05								
	CH-5		71+75	74+17	RT.													242						
	SL-3		74+19		RT.														24					
	LA-17		72+75		RT.																		1	
	LA-18		73+41		RT.																		1	
	LA-19		74+07		RT.																		1	
		CURTIS BLVD.																						
	CLS-2		80+54	82+40	RT.											0.04								
	SL-4		80+54		LT.															23				
<b>TOTALS CARRIED TO SHEET 1054</b>														0.40	0.31	0.32	0.09		1201	155				19

**PAVEMENT MARKING SUBSUMMARY -  
SOM CENTER RD. (S.R. 91)**

**LAK-2-3.32**

CALCULATED	TRR
CHECKED	GJB