SHEET NO.	REFERENCE NO.	LOCATION	STATION	SIDE	CODE	SIZE (INCHES)	630 GROUND MOUNTED SUPPORT, #2 POST FT	630 GROUND MOUNTED SUPPORT, #3 POST FT	630 GROUND MOUNTED SUPPORT, #4 POST EACH	630 GROUND MOUNTED SUPPORT, #6 POST FT	630 ONE WAY SUPPORT, #3 POST FT	630 STREET NAME SIGN SUPPORT, #2 POST FT	630 SIGN SUPPORT ASSEMBLY, POLE MOUNTED, AS PER PLAN EACH	630 SIGN SUPPORT ASSEMBLY, BARRIER MOUNTED EACH	630 SIGN, FLAT SHEET SQ FT	630 SIGN, GROUND MOUNTED EXTRUSHEET SQ FT	630 SIGN, DOUBLE-FACED, STREET NAME EACH	630 CONCRETE MEDIAN BARRIER SIGN BRACKET EACH	630 REMOVAL OF GROUND MOUNTED SIGN AND REERECTION EACH	630 REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL EACH	630 REMOVAL OF POLE MOUNTED SIGN AND DISPOSAL EACH	630 REMOVAL OF GROUND MOUNTED POST SUPPORT AND REERECTION EACH	630 REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL, AS PER PLAN EACH	
1119	R-12	RAMP BF	200+60	CL																2				1	
	S-2		200+66	CL	R4-7B-36	36 X 48		15.0/15.0							12.0										
	R-1		200+72	RT																1				1	
	R-11		200+86	LT																3				1	
	S-9		201+02	LT	R3-H8CP-48	48 X 30					15.5/15.5				10.0										
	S-9		201+02	LT	R5-1-36	36 X 36									9.0										
	S-9		201+02	LT	R6-1L-48	48 X 18									6.0										
	S-9		201+02	LT	R6-1R-48	48 X 18									6.0										
	R-2		201+25	LT			15.0												1					1	
	S-1		201+32	RT	R5-H10E-30	30 X 30		13.5							6.3										
	R-10		201+63	LT																1				2	
	S-3		203+88	LT	R3-H8CP-48	48 X 30	13.5/13.5								10.0										
	R-3		205+54	RT				15.0											1						
		SUBTOTAL					42.0	58.5			31.0				59.3				2	7				6	
		SHEET 1082 TOTAL					15.0	322.5			60.0				194.3				5	20				23	
TOTALS CARRIED TO GEN. SUMMARY							57	381			91				254				7	27				29	

CALCULATED JMM
CHECKED DRJ

LOST NATION RD. RAMPS
GROUND MOUNTED SIGNING SUBSUMMARY

LAK-2-3.32

1083
1679

G:\Project\lak\13486\traffic\sheets\13486TSS013.dgn 6/24/2008 9:29:42 AM djozity