LIGHTING SUBSUMMARY

CALCULATED JMS
CHECKED ZFB

REFERENCE NO.	SHEET NO.	SIDE	ROADWAY	STATION TO STATION	202 PULL BOX REMOVED EA	202 LIGHT TOWER REMOVED, AS PER PLAN EA	202 POWER SERVICE REMOVED, AS PER PLAN EA	202 LIGHT TOWER FOUNDATION REMOVED EA	202 REMOVAL MISC.: UNDERPASS LIGHTING SYSTEM EA	625 CONNECTOR KIT, TYPE II EA	625 CONNECTOR KIT, TYPE III EA	625 CABLE SPLICING KIT EA	625 LIGHT POLE, DECORATIVE, AS PER PLAN EA	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ATLM39 EA	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ATLM20 EA	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ALM35 EA	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ALM15 EA	625 LIGHT POLE ANCHOR BOLTS, MISC.: SET FOR PILASTER OR BARRIER MOUNTED LIGHT POLE EA	625 LIGHT POLE FOUNDATION, 24"x8' DEEP EA	625 MEDIAN LIGHT POLE FOUNDATION, 10' DEEP EA	625 NO. 6 AWG 600 VOLT DISTRIBUTION CABLE FT	625 NO. 1/0 AWG 5000 VOLT DISTRIBUTION CABLE FT	625 NO. 4 AWG 5000 VOLT DISTRIBUTION CABLE FT	625 NO. 2 AWG 5000 VOLT DISTRIBUTION CABLE FT	625 NO. 10 AWG POLE AND BRACKET CABLE FT	625 1-1/2" DUCT CABLE WITH THREE NO. 4 AWG 5000 VOLT CABLES FT	625 1-1/2" DUCT CABLE WITH THREE NO. 2 AWG 5000 VOLT CABLES FT	625 CONDUIT, 1", 725.04 FT	625 CONDUIT, 2", 725.04 FT	625 CONDUIT, 1", 725.05 FT	SEE SHEET 1209 FOR CONTINUATION
R-1	1243	CL	SR 2	309+04.09		1		1																									
R-2	1243	RT	RAMP H	310+16.94		1		1																									
R-3	1243	RT	RAMP E	315+13.76		1		1																									
R-4	1243	LT	RAMP H	316+83.44		1		1																									
R-5	1243	RT	RAMP A	317+44.76		1		1																									
R-6	1243	LT	SR 2	305+23.35	1																												
R-7	1243	RT	SR 2	310+40.65	1																												
R-8	1243	RT	SR 2	313+11.01	1																												
R-9	1243	RT	RAMP E	314+57.86	1																												
R-10	1243	RT	RAMP E	314+57.86			1																										
R-11	1243	RT	RAMP E	314+13.78	1																												
R-12	1243	LT	RAMP A	317+44.74	1																												
R-13	1243	RT	SR 2	310+01.36	1																												
E-1	1243	CL	SR 2	305+00.00-305+88.00																										279			
NB-8	1243	CL	SR 2	305+88.00						2						1					1								70				
E-2	1243	LT	SR 2	305+00.00-306+13.15																									115				
NB-9	1243	LT	SR 2	306+13.15						2				1					1									78					
E-3	1243	CL	SR 2	305+88.00-307+35.13																								471					
NB-11	1243	CL	SR 2	307+35.13						2						1					1							70					
E-4	1243	CL	SR 2	307+35.13-308+72.73																						444							
NB-12	1243	CL	SR 2	308+72.73						2						1					1							70					
E-5	1243	LT	SR 2	306+13.15-309+21.50																									313				
NB-13	1243	LT	SR 2	309+21.50						2				1					1									78					
VA-1	1243	CL	SR 2	310+13.54						2						1					1							70					
E-6	1243	CL	SR 2	310+13.54-313+25.04																					966								
VA-3	1243	CL	SR 2	313+25.04						2						1					1							70					
E-7	1243	CL	SR 2	313+25.04-314+59.65																					435								
VA-4	1243	CL	SR 2	314+59.65						2						1					1							70					
E-8	1243	CL	SR 2	314+59.65-315+99.46																					453	423							
VA-5	1243	CL	SR 2	315+99.46						2						1					1							70					
E-9	1243	CL	SR 2	315+99.46-317+34.34																					435	405							
VA-6	1243	CL	SR 2	317+34.34						2						1					1							70					
E-10	1243	CL	SR 2	317+34.34-318+70.31																					441	411							
VA-7	1243	CL	SR 2	318+70.31						2						1					1							70					
E-11	1243	CL	SR 2	318+70.31-319+50.00																					255	240							
VA-2	1243	LT	SR 2	311+31.57						2						1			1									70					
E-12	1243	LT	SR 2	311+31.57-312+28.94																					330							100		
PB-9V	1243	LT	SR 2	312+28.94								3																					
VA-8	1243	LT	SR 2	314+17.43						2				1					1									78					
E-13	1243	LT	SR 2	314+17.43-314+59.53																										52			
PB-1V	1243	LT	SR 2	314+59.53								3																					
E-14	1243	LT	SR 2	314+59.53-316+72.54																										210			
VA-9	1243	LT	RAMP H	316+72.54						2				1					1									78					
E-15	1243	LT	RAMP H	316+72.54-318+73.74																										192			
VA-10	1243	LT	RAMP H	318+73.74						2				1					1									78					
E-16	1243	LT	RAMP H	318+73.74-319+71.94																										95			
PB-4V	1243	LT	RAMP H	319+71.94								3																					
E-17	1243	RT	RAMP H	312+45.88-319+71.94																										162			
VA-11	1243	RT	RAMP H	312+45.88						2				1					1									78					
TOTALS CARRIED TO GENERAL SUMMARY					7	5	1	5	0	32	0	9	0	6	0	10	0	1	6	9	0	0	3315	2673	1168	711	428	0	100	0			

LAK-2-3.32

1208
1679

g:\project\lak\13486\lighting\sheets\13486LSS005.dgn 7/11/2008 8:59:43 AM dshaner