REFERENCE NO.	SHEET NO.	SIDE	ROADWAY	STATION TO STATION	202 PULL BOX REMOVED	202 LIGHT TOWER REMOVED, AS PER PLAN	202 POWER SERVICE REMOVED, AS PER PLAN	202 LIGHT TOWER FOUNDATION REMOVED	202 REMOVAL MISC.: UNDERPASS LIGHTING SYSTEM	625 CONNECTOR KIT, TYPE II	625 CONNECTOR KIT, TYPE III	625 CABLE SPLICING KIT	625 LIGHT POLE, DECORATIVE, AS PER PLAN	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ATLM39	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ATLM20	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ALM35	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ALM15	625 LIGHT POLE ANCHOR BOLTS, MISC.: SET FOR PILASTER OR BARRIER MOUNTED LIGHT POLE	625 LIGHT POLE FOUNDATION, 24"x8' DEEP	625 MEDIAN LIGHT POLE FOUNDATION, 10' DEEP	625 NO. 6 AWG 600 VOLT DISTRIBUTION CABLE	625 NO. 1/0 AWG 5000 VOLT DISTRIBUTION CABLE	625 NO. 4 AWG 5000 VOLT DISTRIBUTION CABLE	625 NO. 2 AWG 5000 VOLT DISTRIBUTION CABLE	625 NO. 10 AWG POLE AND BRACKET CABLE	625 1-1/2" DUCT CABLE WITH THREE NO. 4 AWG 5000 VOLT CABLES	625 1-1/2" DUCT CABLE WITH THREE NO. 2 AWG 5000 VOLT CABLES	625 CONDUIT, 1", 725.04	625 CONDUIT, 2", 725.04	625 CONDUIT, 1", 725.05	SEE SHEET 1211 FOR CONTINUATION
					EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	
E-18	1243	RT	RAMP H	309+79.06-312+45.88																						277					
VA-12	1243	RT	RAMP H	309+79.06						2				1					1						78						
E-19	1243	RT/LT	RAMP H	319+71.94-314+15.23																			264								
PB-3V	1243	LT	RAMP H	314+15.23								3																			
E-20	1243	LT	RAMP H	311+96.28-314+15.23																						235					
VA-14	1243	LT	RAMP H	311+96.28						2				1					1						78						
E-21	1243	LT	RAMP H	309+59.26-311+96.28																						248					
VA-13	1243	LT	RAMP H	309+59.26						2				1					1						78						
E-22	1243	LT	RAMP H	314+15.23-314+34.61																						32					
VA-15	1243	LT	RAMP H	314+34.61						2				1					1						78						
VA-16	1243	LT	RAMP H	317+28.49						2				1					1						78						
E-23	1243	LT	RAMP H	317+28.49-319+40.02																						213					
VB-1	1243	RT	RAMP E	309+52.82						2				1					1						78						
E-24	1243	RT	RAMP E	309+52.82-311+08.48																						168					
PB-10V	1243	RT	RAMP E	311+08.48								3																			
VB-2	1243	RT	RAMP E	312+06.33						2						1		1							70						
E-25	1243	RT	RAMP E	312+06.33-314+43.49																			720						230		
PB-2V	1243	RT	RAMP E	314+43.49								3																			
E-26	1243	RT	RAMP E	314+43.49-314+46.76																						32					
E-27	1243	RT	RAMP E	314+43.49-315+42.62																						110					
VB-3	1243	RT	RAMP E	315+42.62						2				1					1						78						
E-28	1243	RT	RAMP E	315+42.62-317+69.72																						225					
VB-4	1243	RT	RAMP E	317+69.72						2				1					1						78						
E-29	1243	RT	RAMP E	317+69.72-319+75.14																						185					
PB-5V	1243	RT	RAMP E	319+75.14								3																			
E-30	1243	RT	RAMP E	319+75.14-319+90.18																						25					
VB-5	1243	RT	RAMP E	319+90.18						2				1					1						78						
VB-6	1243	RT	RAMP A	316+66.36						2				1					1						78						
E-31	1243	RT	RAMP A	316+66.36-316+79.32																						23					
PB-6V	1243	RT	RAMP A	316+79.32								3																			
E-32	1243	RT	RAMP A	316+79.32-318+16.36																						147					
E-33	1243	LT	SR 2	312+28.94-314+17.43																						198					
E-34	1243	RT	SR 2	311+08.48-312+06.33																			300						90		
E-35	1243	CL/RT	SR 2/RAMP E	314+59.65-314+46.76																			402	402							
E-36	1243	CL/RT	SR 2/RAMP E	305+88.00-305+89.27																				312							
PB-8N	1243	RT	SR 2	305+89.27								3																			
E-37	1243	RT	SR 2	305+89.27-306+22.02																							44				
NB-10	1243	RT	RAMP E	306+22.02						2				1					1						78						
E-38	1243	RT/LT	RAMP E/VINE	314+46.76-128+31/60																		300							15		
E-39	1243	RT	RAMP E	314+46.76																											
E-40	1243	RT/RT	RAMP E/A	319+75.14-316+79.32																			339								
E-41	1243	LT/CL	RAMP H/SR 2	314+59.53-314+59.65																			330								
VB-7	1243	RT	RAMP A	318+16.36						2				1					1						78						
E-42	1243/1244	RT	RAMP A	318+16.36-319+46.33																						140					
R-1	1244	RT	SR 2	322+06.66		1		1																							
R-2	1244	RT	SR 2	326+21.29		1		1																							
E-1	1244	CL	SR 2	319+50.00-320+08.31																			189	174							
VA-17	1244	CL	SR 2	320+08.31						2						1				1					70						
E-2	1244	CL	SR 2	320+08.31-321+47.23																			447	417							
VA-19	1244	CL	SR 2	321+47.23						2						1				1					70						
E-3	1244	CL	SR 2	321+47.23-322+85.75																			447	417							
TOTALS CARRIED TO GENERAL SUMMARY					0	2	0	2	0	30	0	18	0	12	0	3	0	1	12	2	0	300	3438	1722	1146	2258	44	0	335	0	

CALCULATED JMS
CHECKED ZFB

LIGHTING SUBSUMMARY

LAK-2-3.32

1210
1679

g:\project\lak\13486\lighting\sheets\13486LSS007.dgn 7/11/2008 9:29:45 AM dshaner