LIGHTING SUBSUMMARY

CALCULATED JMS
CHECKED ZFB

REFERENCE NO.	SHEET NO.	SIDE	ROADWAY	STATION TO STATION	202 PULL BOX REMOVED EA	202 LIGHT TOWER REMOVED, AS PER PLAN EA	202 POWER SERVICE REMOVED, AS PER PLAN EA	202 LIGHT TOWER FOUNDATION REMOVED EA	202 REMOVAL MISC.: UNDERPASS LIGHTING SYSTEM EA	625 CONNECTOR KIT, TYPE II EA	625 CONNECTOR KIT, TYPE III EA	625 CABLE SPLICING KIT EA	625 LIGHT POLE, DECORATIVE, AS PER PLAN EA	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ATLM39 EA	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ATLM20 EA	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ALM35 EA	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ALM15 EA	625 LIGHT POLE ANCHOR BOLTS, MISC.: SET FOR PILASTER OR BARRIER MOUNTED LIGHT POLE EA	625 LIGHT POLE FOUNDATION, 24"x8' DEEP EA	625 MEDIAN LIGHT POLE FOUNDATION, 10' DEEP EA	625 NO. 6 AWG 600 VOLT DISTRIBUTION CABLE FT	625 NO. 1/0 AWG 5000 VOLT DISTRIBUTION CABLE FT	625 NO. 4 AWG 5000 VOLT DISTRIBUTION CABLE FT	625 NO. 2 AWG 5000 VOLT DISTRIBUTION CABLE FT	625 NO. 10 AWG POLE AND BRACKET CABLE FT	625 1-1/2" DUCT CABLE WITH THREE NO. 4 AWG 5000 VOLT CABLES FT	625 1-1/2" DUCT CABLE WITH THREE NO. 2 AWG 5000 VOLT CABLES FT	625 CONDUIT, 1", 725.04 FT	625 CONDUIT, 2", 725.04 FT	625 CONDUIT, 1", 725.05 FT	SEE SHEET 1219 FOR CONTINUATION
LF-7	1248	LT	RAMP D	79+12.24						2						1				1							70						
E-19	1248	CL/LT	SR 2	373+27.90-373+27.10																					711							
E-20	1248	CL/RT	SR 2	373+27.90-373+28.37																					270							
PB-21L	1248	RT	SR 2	373+28.37								3																					
E-21	1248	RT	SR 2	373+28.37-373+44.50																									26				
LF-21	1248	RT	SR 2	373+44.50						2						1				1							40						
E-22	1248	RT	SR 2	371+80.40-373+28.37																									156				
LF-22	1248	RT	SR 2	371+80.40						2						1				1							40						
E-23	1248	RT	SR 2	373+44.50-375+36.79																									200				
LF-20	1248	RT	SR 2	375+36.79						2						1				1							40						
R-1	1249	LT	SR 2	386+61.45		1		1																									
R-2	1249	CL	SR 2	383+36.44		1		1																									
R-3	1249	CL	SR 2	389+63.53		1		1																									
R-4	1249	LT	SR 2	392+36.68		1		1																									
R-5	1249	LT	L. NATION	52+52.78		1		1																									
R-6	1249	RT	SR 2	382+50.72	1																												
R-7	1249	LT	RAMP F	203+28.56		1		1																									
R-8	1249	LT	RAMP B	92+28.44		1		1																									
R-9	1249	LT	RAMP F	206+85.75	1																												
R-10	1249	RT	SR 2	386+02.41	1																												
R-11	1249	LT	RAMP F	203+28.69	1																												
R-12	1249	LT	SR 2	391+99.14	1																												
LB-12	1249	CL	SR 2	383+40.43						2						1				1							70						
E-1	1249	CL	SR 2	383+40.43-384+73.92																					432							
LB-13	1249	CL	SR 2	384+73.92						2						1				1							70						
E-2	1249	CL	SR 2	383+40.43-385+75.59																					336							
LB-14	1249	CL	SR 2	385+75.59						2						1				1							70						
E-3	1249	CL	SR 2	385+75.59-387+91.63																					678							
LB-15	1249	CL	SR 2	387+91.63						2						1				1							70						
E-4	1249	CL	SR 2	387+91.63-389+15.96																					405							
LB-16	1249	CL	SR 2	389+15.96						2						1				1							70						
E-5	1249	CL	SR 2	389+15.96-390+49.01																					429							
LB-17	1249	CL	SR 2	390+49.01						2						1				1							70						
E-6	1249	CL	SR 2	390+49.01-391+84.73																					438							
LB-18	1249	CL	SR 2	391+84.73						2						1				1							70						
E-7	1249	CL	SR 2	391+84.73-392+50.00																					210							
E-8	1249	LT/RT	SR 2	388+65.66-388+04.59																					657							
E-9	1249	LT/CL	SR 2	388+65.66-389+15.96																					363							
LB-11	1249	LT	SR 2	382+22.86						2						1		1									70						
E-10	1249	LT	SR 2	382+22.86-383+30.67																					351						107		
PB-20L	1249	LT	SR 2	383+30.67								3																					
E-11	1249	LT	SR 2	383+30.67-386+08.60																									298				
LB-10	1249	LT	SR 2	386+08.60						2					1					1							78						
E-12	1249	LT	SR 2	386+08.60-388+14.07																									220				
LB-9	1249	LT	SR 2	388+14.07						2					1					1							78						
E-13	1249	LT	SR 2	388+14.07-388+65.66																									63				
PB-9L	1249	LT	SR 2	388+65.66								6																					
LB-3	1249	LT	RAMP E	102+68.78						2					1					1							78						
TOTALS CARRIED TO GENERAL SUMMARY					5	7	0	7	0	30	0	12	0	3	3	9	0	1	6	8	0	0	4299	981	984	581	382	0	107	0	

LAK-2-3.32

1218
1679

g:\project\lak\13486\lighting\sheets\13486LSS015.dgn 7/11/2008 9:30:27 AM dshaner