

**Proposal Addendum
For
LAK-2-3.32; PID 13486
Project 080597**

Revised Bid Items:

Ref. No.	Item Number	Quantity	Unit	Description
513	509E10001	109,168	LB	Epoxy Coated Reinforcing Steel, As Per Plan
553	509E10001	109,627	LB	Epoxy Coated Reinforcing Steel, As Per Plan
834	509E10001	53,632	LB	Epoxy Coated Reinforcing Steel, As Per Plan
854	509E10001	53,458	LB	Epoxy Coated Reinforcing Steel, As Per Plan
931	606E10310	126,752	SF	Special – Noise Barrier (Absorptive), Over 10' to 14' Height
936	606E10920	4391	SF	Special – Noise Barrier, Misc.: Structure Mounted TL-4 Noise Barrier
944	619E16021	36	MNTH	Field Office, Type C, As Per Plan

Replace all notes in the plans referring to Item 511 – Class HP Concrete with the following note:

- Item 511 – Class HP Concrete, Bridge Deck, As Per Plan**
- Item 511 – Class HP Concrete, Bridge Deck (Parapet), As Per Plan**
- Item 511 – Class HP Concrete, Substructure, As Per Plan**
- Item 511 – Class HP Concrete, Superstructure, As Per Plan**
- Item 511 – Class HP Concrete, Sidewalk, As Per Plan**
- Item 511 – Class HP Concrete, Test Slab**

General Requirements:

The provisions of Item 511, shall apply except as noted below.

Mix Options:

All superstructure, bridge deck, sidewalk, parapet, median barrier and approach slab concrete shall be this mix, as modified by Table A. All other structure concrete shall be this mix, as modified by Table B.

The following proportions will be used as a starting mix design: