

**Proposal Addendum  
For  
LAK-2-3.32; PID 13486  
Project 080597**

**Revised Bid Items:**

<b>Ref. No.</b>	<b>Item Number</b>	<b>Quantity</b>	<b>Unit</b>	<b>Description</b>
423	614E12756	3	Each	Work Zone Crossover Lighting System
206	625E10500	174	Each	Light Pole Misc.: Design ALM35

**Please revise the proposal note:**

**“PN 090 - 7/21/2006 - Work Type Codes and Descriptions”** the third paragraph shall read: ‘Listed below are the work types for this proposal. In accordance with Ohio Law, a bidder must possess work types, and perform work equal to at least forty percent of the total amount of the submitted bid price.’

Prebid Questions from prebid meeting 10/30/08:

Q: There is discrepancy in the crossover lighting quantity.

A: The crossover lighting quantity has been revised to 3 in addendum #5.

Q: Does ODOT want to keep the temporary lighting in the plans?

A: Yes, for safety reasons.

Q: It appears that there is not enough quantity of temporary signals.

A: The only actual temporary signal installation is at the EB exit ramp at Vine Street, all others are changes to phasing, timing or head locations covered under the maintenance of traffic signal/flasher installation note on sheet 51.

Q: Does ODOT want break away poles on top of the median barrier?

A: No. The poles are called out correctly on the plan sheets, but the description was incorrect in the lighting general summary. See addendum #5.