

Asbestos.

A copy of the Ohio Environmental Protection Agency (OEPA) Notification of Demolition and Renovation forms with sections I-VII and XVI completed is included with the bid package. A copy of these form signed by the bridge owner will be provided to the successful bidder. The Contractor will complete sections VIII-XIII of the signed forms and submit the completed forms to the Local Air Authority at least ten (10) days prior to reconstruction of the bridges. The Contractor will provide a copy of the completed form to the Engineer. The Local Air Authority is:

**Attn: Bert Mechenbier  
Lake County  
Air Pollution Control  
33 Mill Street  
Painesville, Ohio 44077**

A copy of the Ohio Department of Health notification form is also included with the bid package. A copy of this form must be completed and submitted to the Ohio Department of Health at least ten days (10) prior to the reconstruction of the bridges. The Contractor will provide a copy of the completed forms to the Engineer. The address is:

Ohio Department of Health  
Asbestos Program  
246 North High Street  
P.O. Box 118  
Columbus, Ohio 4326-0118

The Contractor will provide an individual trained in the provisions of NESHAP that will be on-site during removal of the asbestos containing materials. In addition to the asbestos containing material identified in the Asbestos Survey Report, this individual will also, monitor any additional non-visible asbestos encountered within the project work limits.

The Contractor will furnish all labor, equipment, and materials necessary to complete, submit, and comply with the OEPA Notification form and to remove, transport, and dispose of the materials containing asbestos from within the project work limits. Payment of this work will be included in the bid Lump Sum price Item Special - Asbestos Abatement.

**Item  
Item Special - Asbestos Abatement**

**Unit  
Lump Sum**

**Answers to Prebid Questions:**

Q: Bid item 171 622 Single Slope Barrier, APP. B-2 on sheets 292-293 and B-1 on sheet 580 is the same piece and is listed twice in the summary tables. Also does there need to be a bid item for Single Slope Barrier APP End Section where abutting the attenuators - what about End Anchors at the ends of some of the runs?

A: The quantities have been revised in this addendum.

Q: The inlet, sign and light foundation wall sections have not been deleted from the total length of the type B, B1 and D barrier wall items.

A: The quantity has been revised in this addendum.

Q: Sheet 261 shows Type D barrier wall for sheet 580 references B-2(56 LF) and B-3(57 LF).