

- The Lost Nation Rd. interchange work shall include the reconstruction and realignment of Lost Nation Rd., replacement of the Lost Nation Rd. bridge, reconstruction of the Oak Hill Lane and Reeves Rd. intersections, reconstruction and realignment of Ramp A from the Lost Nation intersection to Sta. 89+85, Ramp E from the Lost Nation intersection to Sta. 97+85, Ramps B and F from the Lost Nation intersection to Sta. 205+00, Ramp D from the Lost Nation intersection to Sta. 89+00, new drainage, signing, pavement markings, the removal of the high mast lighting and install temporary lighting.
 1. Prior to beginning work at the SR-2/Lost Nation Rd. interchange, the contractor shall remove the high mast towers at the interchange which shall be completed prior to setting up work zones on Lost Nation Rd. and SR-2.
 2. During construction, Lost Nation Ramps A, E, B and F can be closed for 45 days each. See sheet 179 for detour details.
 3. For Lost Nation Rd., one lane (11' min.) in each direction on Lost Nation Rd. shall be maintained at all times.
 4. Reeves Rd. shall be detoured as per sheet 187 when constructing the Lost Nation Rd./Reeves Rd. intersection.
 5. When constructing the Lost Nation Rd./Oak Hill Lane intersection, one lane of traffic shall be maintained for Oak Hill Lane.

- The culvert lining work and related construction activities at Sta. 308+66.09, centerline SR-2 and at E 367 St. shall be completed by the contractor in Stage 1, by June 1, 2009.
 1. Vehicular access to the properties south of Lakeland Blvd. E. 367th must be maintained at all times during construction operations.

- Construct the 8'x5' and 42" culverts at Sta. 336+05 and Sta. 345+16, respectively. The contractor shall construct the outlet end first which will require the closing of Stevens Blvd. Stevens Blvd. shall only be closed for one weekend.
 1. If needed, the contractor is limited to three weekend one lane closures of SR-2 (10 PM Fri to 6AM Mon) to facilitate the construction of the 8'x5' and 42" culverts which shall be at the approval of ODOT. The contractor shall contact the surrounding cities and ODOT 18 days prior to closing SR-2 to one lane.
 2. Stevens Blvd. traffic shall be detoured as per sheet 183 for one weekend only (10 PM Fri to 6AM Mon).

- The following construction activities shall also be constructed during this phase:
 - **Metro Park Retaining Wall.**
 - Newell Creek bridges
 - Lost Nation Rd. Ramp D bridge.
 - Chagrin River Substructure work in the river.
 - Culvert at Sta. 341+45
 - Wall #3 (Lost Nation Rd.)

- The following construction activities may be constructed during this phase (work may commence in Stage 1 but does not have to be completed prior to starting Stage 2):