

- East 361<sup>ST</sup> St. left structure.
- Erie St. bridge substructure work.

For Stage 2, the following must be completed:

- Reconstruct SR-2 pavement, full width, including the median barrier, new drainage and signing from Sta. 351+25 to Sta. 420+00. (Note: due to the elevation differences between the old and new pavement at Sta. 351+25, a temporary pavement tie-in may be required).
- For the Lost Nation interchange, reconstruct and realign the remainder of Ramps A, E, B, F and D.
  1. During construction, Lost Nation Ramps A, E, B and F can be closed for 45 days each. See sheet 179 for detour details.
- The following construction activities shall also be constructed during this phase:
  - Erie St. Bridge.
  - Chagrin River Bridge.
  - Erie St. Retaining Wall

For Stage 3, the following must be completed:

- Reconstruct SR-2 pavement, full width, including the median barrier, new drainage and signing from Sta. 276+00 to Sta. 351+25.
  1. During construction of SR-2 and Vine St. during Stage 3, the westbound entrance ramp on the south side of Vine St. may only be closed during the AM peak (6AM to 10 AM, Mon. – Fri.) hours and detoured per sheet 177.
- The SOM Center Rd. work shall include the reconfiguration and widening of SOM Center Rd. and the reconstruction of Ramp A and B, new drainage, signing and pavement markings.
  1. During Stage 3 construction, when SOM Center Rd. Ramp A remains open it shall be closed during PM Peak hours (3 PM to 6 PM, Mon. – Fri.) and detoured as per sheet 175.
  2. During construction, SOM Center Rd. Ramps A and B can be closed for 45 days each. See sheet 175 for detour details.
  3. SOM Center Rd. Ramps C and D shall remain open at all times.
  4. SOM Center Rd. shall be completed in part-width construction, maintaining one 11' thru lane of traffic in each direction and the northbound left turn lanes at Ramp D and Curtis Blvd.
- The Vine St. interchange work shall include the reconfiguration and widening of Vine St. the reconstruction and realignment of Ramp A, D, E and H, new drainage, signing and pavement markings.
  1. During construction, Vine St. Ramps A, D, E and H can be closed for 45 days each. See sheet 176 for detour details.
  2. A minimum of one lane (11' min.) in each direction along with one left turn lane onto the