

entrance ramps shall be maintained on Vine St. in the interchange area.

- Lakeland Blvd. shall be constructed in two phases, and shall coincide with the work on the south side of Vine St.
 1. Access shall be maintained to the local businesses on Lakeland Blvd. throughout each phase of construction.
 2. Each phase shall be completed within thirty (30) calendar days and opened to traffic using part width construction. Liquidated damages in accordance with the C&MS Table 108.07-1 or as revised in the Contract Documents shall be assessed for each Calendar day phased work extends beyond that required herein.
- The following construction activities shall also be constructed during this phase:
 1. Vine St. Retaining Wall.
 2. East 361ST St. right structure.
 3. Vine St. bridge

Stage 4 (Asphalt Alternative), the following must be completed:

- Stage 4 shall consist of placing the final surface course over the entire roadway surface of the mainline and ramps, final pavement markings, raised pavement markers and all work completed.
 1. Traffic shall be maintained in accordance with the permitted lane closure note.

Stage 4 (Concrete Alternative), the following must be completed:

- Stage 4 shall consist of placing the final pavement markings, raised pavement markers and all work completed.
 1. Traffic shall be maintained in accordance with the permitted lane closure note.

Develop all necessary changes to the Department accepted Contractor Prepared MOT Plan, to implement the work and to effectively manage traffic and operations, in accordance with the Contract Documents and the identified intent, in accordance with the provisions of this item. Provide the Department three (3) copies of all MOT Plan changes made during the prosecution of the work. If during the prosecution of work, errors are identified in the Contractor Prepared MOT Plan, revisions to the plan shall be developed and provided to the Department. Develop and provide MOT Plan modifications requested by the Department during the prosecution of the work to bring the plan into compliance with the Contract Documents.

Any payment for changes to the Contract Prepared MOT Plan requested by the Department to facilitate the performance of Department directed extra work will be resolved in accordance with the Contract Document change order provisions.

Payment for all work provided for within this item and any changes to the work for this item shall be included within and accounted for by the Bidder at the unit price bid for each Item 614 – Maintaining Traffic, Misc.: Contractor Prepared Maintenance of Traffic Plan (by Type).

Maintaining Traffic: