

Added Bid Items:

Ref. No.	Item Number	Quantity	Unit	Description
1047	254E01000	7572	SY	Pavement Planing, Asphalt Concrete
1048	448E46050	661	CY	Asphalt Concrete Intermediate Course, Type 2, PG64-22
1049	448E47020	472	CY	Asphalt Concrete Surface Course, Type 1, PG64-22
1050	622E40046	3059	FT	Portable Concrete Barrier, 50", Bridge Mounted
1051	509E10000	1553	LB	Epoxy Coated Reinforcing Steel
1052	511E46600	9.5	CY	Class C Concrete, Headwall
1053	603E16600	20	FT	36" Conduit, Type C
1054	603E16200	211	FT	36" Conduit, Type A, 706.02 (1250 D Load)

Deleted Items:

Ref. No.	Item Number	Quantity	Unit	Description
72	671E15030	2000	SY	Erosion Control Mat, Type D
103	603E16400	21	FT	36" Conduit, Type B

Revised Plan Sheets Linked to this Addendum

Plan sheet 960/1679
Plan sheet 248, 249,250, 251, 252, 253, 254, 255
Plan sheet 261
Plan sheet 1647

Reports are attached to this Addendum

Asbestos abatement inspection report for parcel 9, dated 3/24/08 for the Building Demolition at 36628 Vine St.

Special Provisions are attached to this Addendum

Special Provisions, 404 Permit

Spreadsheet linked to this Addendum

Rebar list for headwalls

Revise the following sheets:

The cross section sheets 714-716 incorrectly show pavement to be removed, please disregard.

Clarification on the plan note on sheets 1274 and 1465, Inspection of Existing Structural Steel: The contractor can assume, for repair of cracks, a hole drilling per crack found.

Revise Sheet:

Revise sheet 1603/1679, under section A-A, the porous backfill is to REMAIN instead of being removed.

Revised plan sheet 1647/1679 to include a 75' x 45' temporary parking pad using 375 SY of Item 615E25000 - Pavement For Maintaining Traffic, Class B (linked to this addendum).