

**Proposal Addendum
For
LAK-2-3.32; PID 13486
Project 080597**

Revised the following Items:

Ref. No.	Item Number	Quantity	Unit	Description	TRAC	Major Rehab
1050	622E40047	3059	FT	Portable Concrete Barrier, 50", Bridge Mounted, As Per Plan	2294	765

Add the following notes:

Bridge mounted portable concrete barrier, 32 inches high with an 18 inch minimum height glare screen shall be used. The glare screen shall be constructed using one of the screens provided on the approved list, available on the Office of Material Management web page at <http://www.dot.state.oh.us/testlab/applists/misc/glare screen.htm>.

Paddle or intermittent type glare screens shall be designed using a 20 degree cut off angle based on tangent alignment. That spacing shall be used throughout the barrier length without regard to barrier curvature.

The glare screen system shall be securely fastened to the 32 inch bridge mounted portable concrete barrier using the hardware and procedures specified by the manufacturer.

Payment shall include all labor, material and equipment necessary to perform the work and shall be paid for at the contract price per foot for Item 622, Bridge Mounted Portable Concrete Barrier, 50", As Per Plan.

Any reference in the bidding documents to October 1st as the winter time limitation shall read November 1st. By November 1st of each year, complete all pavement work (up to and including the proposed intermediate course, for the asphalt alternative) required for the affected stage of construction and return traffic to un-shifted position with full lane widths.

Answers to Prebid Questions:

Q: Addendum 10 addressed in the maintenance of traffic in requirement #12 that all normal lanes of traffic shall be open to unrestricted traffic from November 1 through March 1. Does this mean the winter time limitation note #1 on plan sheets 53 and 56G should be changed from October 1 to November 1? Also, winter time limitation note #2 states that traffic shifts for bridge work may remain in place between November 1 and March 1. Does this still apply?

A: The winter time restriction has been changed to November 1st in this addendum. Yes bridge work may remain in place between November 1st and March 1st with the limitations specified in the winter time limitations note #2.

Q: Addendum No. 11 added reference No.1050, Portable Concrete Barrier 50" Bridge Mounted. Per SCD RM-4.1 (10/20/06) wall is not to be used on bridge deck edges or similar drop-offs. The only suitable barrier is 32" PCB per Structural Engineering's Standard Drawing PCB-91 (7/19/02). Please advise, there is no 50" approved Bridge Mounted Portable Concrete Barrier for ODOT.

A: Portable concrete barrier 50", bridge mounted as per plan has been added to this addendum. Use 32" PCB bridge mounted with 18" high glare screen.