

**Proposal Addendum
For
LAK-2-3.32; PID 13486
Project 080597**

Revise the following Items:

Ref. No.	Item Number	Quantity	Unit	Description
30	604E38500	10	Each	Monument Assembly
455	503E21101	205	CY	Unclassified Excavation, As Per Plan
480	503E21101	4511	CY	Unclassified Excavation, As Per Plan
939	604E38500	57	Each	Monument Assembly
1032	304E20000	72509	CY	Aggregate Base

Revise sheet 953:

The callouts and dimension lines for "WALL QUANTITIES" and "ROADWAY QUANTITIES" at the bottom of the Section A-A should be removed. The hatch for the fill material should be extended to the cutline that the excavation limits are currently extended too. The legend note should be revised to read "FILL MATERIAL TO BE INCLUDED WITH ROADWAY ITEM 203 FOR PAYMENT" instead of "FILL MATERIAL TO BE INCLUDED IN WALL QUANTITIES FOR PAYMENT."

Add Note:

Longitudinal tining as per SS 800, dated 10-17-2008 is approved by the Director. Should Concrete Pavement be the awarded alternate, the successful bidder will provide longitudinal tinning as per SS 800 dated 10-17-08. Reference is made to PN 420 for surface smoothness requirements, including corrective action.

In response to a pre-bid question, existing plan sheets are linked to the internet address listed on the cover page of this addendum.