

length of closure to extend beyond 45 days?

Also, to confirm addendum 10, under stage 1 work to be completed notes, ramps A,E,B,F can be closed for 45 days. Stage 2 work to be completed notes also state that ramps A,E,B,F can be closed 45 days. The disincentive table shows 45 days closure with disincentives after 45 days. Please confirm whether or not the contractor will be allowed two closures of up to 45 days at these respective ramps.

- A: As stated in Addendum 10, Ramps A, E, B and F can be closed for 45 days each during Stage 1, when the Lost Nation Rd bridge will be reconstructed and the approach pavement will be replaced. Also, as stated in Addendum 10, Ramps A, B and F can be closed for 45 days each during Stage 2, when the SR-2 pavement will be replaced. During Stage 2, the 45 day closure restriction for Ramp E shall be waived due to the lack of acceleration length that would be required when the SR-2 WB traffic is placed on the outside shoulder to construct the median pavement.
- Q: Does item # 404 - "11 in Reinforced Concrete Pavement" - 6563 sy (set up in MOT plans page 53 of 1679) get removed or does it stay in place upon completion of the project? If it gets removed how is the pavement removal paid for?
- A: If the successful bidder elects to utilize crossovers in their MOT plans, the reinforced concrete may be used in areas of unsuitable soil. The pavement would require removal. Any removal should be accounted for in the Lump Sum MOT quantity.
- Q: Please clarify how the quantities were determined for Ref. 47 and 48. What is this material, and where is it located?
- A: There is a general note on sheet 46B/1679 which explains the quantities for reference numbers 47 and 48. The special provisions asbestos inspection report for parcel 9, dated 3/24/08 describes the materials found and where they are located.
- Q: The lump sum Asbestos Abatement item (Ref. 49) has notes on plan sheet 46/1679 that are confusing. Several of the structures listed there are not even within the scope of this project. For the structures that are in this project, why are the Square Foot and Linear Foot quantities shown not part of Ref. 47 and 48?
- A: Ref item 49 refers to the asbestos removal from the bridges which will be paid as a lump sum. The Item Special - Asbestos Abatement note has been revised in a previous addendum.
- Q: In the Special Provision "Ohio EPA Notification of Demolition Renovation", the reports seem to correspond to the items listed for the lump sum Ref. 49. However, the reports that quantify asbestos containing materials show the materials as being "Non Friable Asbestos Material NOT to be Removed, Category I". Do these materials need to be removed as part of this project?
- A: The Item Special - Asbestos Abatement note has been revised in a previous addendum.
- Q: Also in the asbestos Special Provision, several structure are reported as having asbestos, but no material or quantity is mentioned.
- A: The Item Special - Asbestos Abatement note has been revised in a previous addendum.
- Q: For the Building Demolition, the plan notes on Sheet 46A state that asbestos abatement will be performed by the contractor. Where is this work to be paid for? Are there asbestos reports indicating what needs to be removed?
- A: The asbestos removal for the building to be demolished at 36628 Vine St. will be paid under ref items 47 and 48. A detailed report indicating what needs to be removed can be found in Special Provisions - Asbestos Inspection Report for Parcel 9, dated 3/24/08.