

**Proposal Addendum  
For  
LAK-2-3.32; PID 13486  
Project 080597**

**Revise the following Items:**

Ref. No.	Item Number	Quantity	Unit	Description
41	608E4900	22	Each	Curb Ramp
425	614E13000	225	CY	Asphalt Concrete for Maintaining Traffic
448	616E10000	3155	MGA L	Water

**Delete the following items:**

Ref. No.	Item Number	Quantity	Unit	Description
401	410E12000	480	CY	Traffic Compacted Surface, Type A

**Added Items:**

Ref. No.	Item Number	Quantity	Unit	Description
1064	608E52000	75	SF	Curb Ramp
1065	613E41300	66	CY	Low Strength Mortar Backfill, Type 2

Delete the following note:

Sheet 48/1679 and Sheet 56B/1679 Item 614, Maintaining Traffic (Estimated Quantities).

Revise the following notes:

Sheet 53/1679 and Sheet 56G/1679 Unsuitable Soils at Crossover Locations should read:

Unsuitable soils may be encountered at crossover locations. The following quantities are provided for use by the contractor, if crossovers are utilized.

395	204E13000	1530	CY	Excavation of Subgrade
396	204E30010	1530	CY	Granular Material, Type B
399	304E20000	815	CY	Aggregate Base
404	451E15500	6563	SY	11" Reinforced Concrete Pavement

Sheet 52/1679 and Sheet 56F/1679 Drainage Items During Construction:

Delete the wording "as directed by the engineer".

Sheets 17B and 17C have been revised and linked to this addendum in order to include changes to the concrete median barrier details.