

# QUANTITY SUB-SUMMARIES

TRAFFIC CONTROL					630	630	630	630	630	630
REF.	EXISTING STATION AND OFFSET	RELOCATING STATION AND OFFSET	SIGN LEGEND	SIGN CODE	GROUND MOUNTED SUPPORT, NO.3 POST	STREET NAME SIGN SUPPORT	SIGN ATTACHMENT ASSEMBLY	SIGN, FLAT SHEET, TYPE G	SIGN, DOUBLED FACED, STREET NAME, TYPE G	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL
					UN.FT.	EACH	EACH	SQ.FT.	EACH	EACH
TC-1	STA. 30+20, 30'RT.	STA. 30+18, 32'RT.	STOP	R-1-36	1		1			
TC-2	STA. 30+20, 30'RT.	STA. 30+18, 32'RT.	4-WAY	R-1A-12			1			
TC-3	STA. 30+21, 34'RT.	STA. 30+20, 35'RT.	STREET NAME	D-14-VAR.		1			2	
TC-4	STA. 30+42, 21'LT.	STA. 30+42, 21'LT.	LEFT REV. CURVE	W-18-30	1		1			1
TC-5	STA. 30+42, 21'LT.	STA. 30+42, 21'LT.	SLOW	-			1			
TC-6	STA. 30+43, 25'LT.	STA. 30+43, 25'LT.	NO TRUCKS	R-142-24	1		1			1
TC-7	STA. 30+43, 25'LT.	STA. 30+60, 17'LT.	STOP	R-1-36	1			9.0		
TC-8		STA. 30+60, 17'LT.	4-WAY	R-1A-12				0.5		
TOTALS					4	1	5	9.5	2	3

ROADWAY											
REF.	LOCATION	LIN.FT.	EACH	EACH	LIN.FT.	LIN.FT.	EACH	EACH	EACH	EACH	
R-1	STA. 25+98.00, 20.5'LT. TO STA. 26+96.39, 19'LT.	25.0	1	1	62.50						
R-2	STA. 26+19.13, 19'RT. TO STA. 26+70.34, 19'RT.	12.5	1	1	25.0						
R-3	STA. 29+83.76, 19' RT. TO STA. 30+23.48, 38.62'RT.	12.5	1	1	12.5						
R-4	STA. 30+17.68, 19'LT. TO STA. 30+68.81, 20.47'LT.	12.5	1	1	12.5						
R-5	STA. 26+78, 23'RT. TO STA. 26+85, 19'RT.				8.0					8.0	
R-6	STA. 27+14, 19'LT. TO STA. 27+12, 27'LT.				8.0					8.0	
R-7	STA. 29+61, 26'RT. TO STA. 29+65, 19'RT.				8.0					8.0	
R-8	STA. 29+95, 19'LT. TO STA. 30+03, 23'LT.				8.0					8.0	
TOTALS		62.5	4	4	32	112.5	3	1	2	2	32

DRIVEWAY						304
REF.	LOCATION	LENGTH	WIDTH	DRIVEWAY AREA *	SIDE	8" AGGREGATE BASE
		LIN.FT.	LIN.FT.	SQ.FT.	SIDE	CU.YD.
DR-1	STA. 26+11.60	35.0	11.0	230.4	RT.	5.7
TOTALS						5.7

\* AREA FROM COMPUTER CALCULATION

EROSION CONTROL			601
REF.	LOCATION	SQ.YD.	SLOPE PROTECTION, MISC. GROUT FILLED FABRIC MATS
E-1	STA. 27+03 TO STA. 27+28	192	
E-2	STA. 29+32 TO STA. 29+78	341	
TOTALS		533	

DRAINAGE				604
REF.	LOCATION	EACH	MANHOLE ADJUSTED TO GRADE	
D-1	STA. 26+09.76, 5.70'RT.	1		
D-2	STA. 26+43.54, 12.35'RT.	1		
D-3	STA. 30+15.51, 5.98'LT.	1		
D-4	STA. 30+33.02, 1.22'LT.	1		
TOTALS			4	

FOR PLAN AND PROFILE SEE SHEETS 12-13