



- NOTES:**
1. Include With Approach Slab For Payment.
 2. A 2" Wide Band of Concrete, 2" Deep, Shall Be Chipped Out Around The Perimeter of The Existing Weepholes Prior To Grouting.
 3. The 2" PEJF Placed At The Abutment Face Is Included With Item 601-Slope Protection Misc.: Grout Filled Mats, For Payment
 4. All Reinforcing Steel Clearances From Face of The Concrete Shall Be 2" Unless Shown Otherwise.
 5. For Rear Abutment Demolition And Repair Drawings, See Sheet 7/20.
 6. For Rear Abutment Plan And Elevation, See Sheet 10/20.
 7. NOTATION: C.J.- Construction Joint; EL.- Elevation; E.F.- Each Face; F.F.- Far Face; Ser.- Series; Dws.- Dowels; T. & B.- Top & Bottom; Eq.-Equally; P.E.J.F.- Preformed Expansion Joint Filler; Rt.-Right; Lt.-Left; Min.-Minimum; Typ.-Typical; Brg.-Bearing; Clr.-Clear.

CT Consultants, Inc.
 Engineers • Architects • Planners
 Willoughby • Mentor • Columbus • North Canton • Oakfield

11/20

REAR ABUTMENT DETAILS

BRIDGE NO. LAK-2-0451
 S.R. UNDER STEVENS BLVD.
 LAKE COUNTY

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED DATE	REVISED
I.A.S.	I.A.S.	I.A.S.	J.P.R.	J.E.A. 2-25-94	

NOTE: See Section A-A For Concrete Sealer Limits