GENERAL SUMMARY

SHEET NUMBER 7	8	10	14A	ITEM	ITEM EXT	TOTAL	UNIT	DESCRIPTION
								PAVEMENT
		761		301	10002	761	Cu. Yd.	Bituminous Aggregate Base, AC-20
		1518		304	20001	1518	Cu. Yd.	Aggregate Base, As Per Plan (SEE SHT. 7)
		1518		310	12001	1518	Cu. Yd.	Subbase, Type I, Grading A, As Per Plan (SEE SHT. 7)
		1080		404	20000	1080	Cu. Yd.	Asphalt Concrete, AC-20
		280		622	23400	280	Lin. Ft.	Concrete Barrier, Type B.
		12948		622	24001	12948	Lin. Ft.	Concrete Barrier, Type D, As Per Plan. (SEE SHT. 14)
								LIGHTING
			2	625	01004	2	Each	Connector kit, Type VII B
			984	625	23200	984	Lin. Ft.	No. 4 AWG 5000 Volt Distribution Cable
			5	625	25500	5	Lin. Ft.	Conduit, 3", 713.04
			5	625	29002	5	Lin. Ft.	Trench, 24" Deep
			1	625	31501	1	Each	Median Pull Box, As Per Plan (SEE SHT. 14A)
								TRAFFIC CONTROL
	4			630	85000	4	Each	Removal Of Ground Mounted Sign And Storage
	2			630	86006	2	Each	Removal Of Ground Mounted Post Support And Storage
Lump				614	11000	Lump		Maintaining Traffic
Lump				623	10000	Lump		Construction Layout Stakes
Lump				624	10000	Lump		Mobilization

04-OCT-89 BNCAD>LAND>BNHSUM1