

# PAVEMENT REPLACEMENT SUB-SUMMARY

FHWA REGION	STATE	PROJECT	
5	OHIO		

LAKE COUNTY  
LAK-2-6.14

PAVEMENT JOINT REPAIR			
APPROX. STATIONS	LANE NO.	202	305
		PAVEMENT REMOVED	16" CONC. BASE, AS PER PLAN
		SQ. YDS.	SQ. YDS.
CITY OF MENTOR			
232+50	1,2	16	16
233+00	1,2	16	16
234+70	1,2	16	16
244+10	5,6	16	16
248+25	5,6	16	16
252+00	1,2	16	16
269+50	5	8	8
281+90	5	8	8
329+00	5,6	16	16
358+00	1,2	16	16
360+00	2	8	8
360+50	1,2	16	16
367+90	2	8	8
422+80	1,2	16	16
446+20	5,6	16	16
483+60	5,6	16	16
483+70	2	8	8
529+80	5,6	16	16
534+50	1,2	16	16
534+72	1,2	16	16
538+80	5,6	27	27
575+30	5,6	16	16
**ADDITIONAL		3500	3500
TOTAL MENTOR		3823	3823
PAINESVILLE TWP.			
611+50	2	8	8
631+75	1	16	16
**ADDITIONAL		675	675
TOTAL PAINES. TWP.		699	699

PAVEMENT REPLACEMENT			
APPROX. STATIONS	LANE NO.	202	305
		PAVEMENT REMOVED	10" CONC. BASE, AS PER PLAN
		SQ. YDS.	SQ. YDS.
CITY OF MENTOR			
235+00	5,6	53	53
261+50	1	27	27
272+20	2	27	27
293+80	2	67	67
297+75	6	33	33
325+00	1,2	53	53
328+00	6	67	67
346+00	5,6	267	267
348+00	1,2	200	200
362+00	6	40	40
382+50	1,2	53	53
384+75	5,6	80	80
421+00	1	67	67
421+50	6	40	40
439+56	6	67	67
450+00	6	33	33
450+90	1,2	53	53
453+25	5	33	33
470+00	2	27	27
513+20	6	33	33
544+00	5,6	133	133
563+20	6	33	33
573+00	6	67	67
576+50	2	27	27
**ADDITIONAL		17000	17000
TOTAL MENTOR		18580	18580
PAINESVILLE TWP.			
590+75	5	27	27
608+00	2	67	67
610+75	6	33	33
641+50	6	40	40
648+50	5	40	40
**ADDITIONAL		3700	3700
TOTAL PAINES TWP.		3907	3907

++ ADDITIONAL LOCATIONS AS REQUIRED AND DETERMINED BY THE ENGINEER.

FOR PAVEMENT JOINT REPAIR DETAILS AND PAVEMENT REPLACEMENT DETAILS SEE SHEET 43

THESE TABLES ARE FOR INFORMATION ONLY, EXACT LOCATIONS SHALL BE AS DETERMINED BY THE ENGINEER.