

TRAFFIC CONTROL QUANTITIES

PAVEMENT MARKINGS

ROADWAY	SIDE	STATION		EDGE LINE (WHITE) LIN. FT.	EDGE LINE (YELLOW) LIN. FT.	4" LANE LINE LIN. FT.	847			LANE ARROWS EACH	WORD "ONLY" ON PAVEMENT EACH
		FROM	TO				8"	24"	24"		
							CHANNEL LINE (WHITE) LIN. FT.	STOP LINE LIN. FT.	BROAD TRANSVERSE LINE (WHITE) LIN. FT.		
PAINESVILLE TOWNSHIP											
S.R. 2 EASTBOUND		586 + 22	597 + 60	1138	1138	1138					
		597 + 60	600 + 25	265	265	530					
		600 + 25	602 + 93		268	268	268			126	
		602 + 93	624 + 87	2194	2194	2194					
		624 + 87	626 + 60	173	173	346					
		626 + 60	652 + 50	2590	2590	2590					
S.R. 2 WESTBOUND		586 + 22	596 + 45	1023	1023	1023					
		596 + 45	598 + 70	225	225	450					
		598 + 70	624 + 55	2585	2585	2585					
		624 + 55	627 + 20		265	265	265			125	
		627 + 20	629 + 85	265	265	530					
		629 + 85	658 + 00	2815	2815	2815					
RAMP I-2		20 + 85	43 + 20	2235	2235						
		43 + 20	45 + 85	265			265				
RAMP I-4		1 + 00	3 + 65	265			265				
		3 + 65	16 + 65	1300	1300						
		16 + 65	17 + 40	75			75				
TOTAL PAINESVILLE TWP.				17413 = 3.30 MI.	17341 3.28 MI.	14734 = 2.79 MI.	1138			251	
CITY OF PAINESVILLE											
S.R. 2 EASTBOUND		652 + 50	658 + 00	550	550	550					
TOTAL CITY OF PAINESVILLE				550 = 0.10 MI.	550 = 0.10 MI.	550 = 0.10 MI.					