PARTICIPATION:

I CITY, STATE, & FEDERAL
II STATE & FEDERAL

GENERAL SUMMARY

(A) CITY OF MENTOR
(B) PAINESVILLE TOWNSHIP
(C) CITY OF PAINESVILLE

FHWA REGION	STATE	PROJECT	
5	OHIO		

LAKE COUNTY
LAK-2-6.14

ITEM	SHEET NUMBER 101 A	101 B	101 C	102 A	102 B	102 C	104 A	105 B	105 C	110 A	111 B	111 C	I CITY OF MENTOR	I CITY OF PAINESVILLE	II PAINESVILLE TOWNSHIP	ITEM	QUANT.	UNIT	DESCRIPTION
620																			
620	393	86	1										393	1	86	620	480	EACH	DELINEATOR, TYPE C, FLEXIBLE POST MOUNTED
620	2	7											2		7	620	9	EACH	DELINEATOR, TYPE C, BRACKET MOUNTED
620	127	16											127		16	620	143	EACH	DELINEATOR, TYPE D, FLEXIBLE POST MOUNTED
621							33.51	6.58	0.20				33.51	0.20	6.58	621	40.29	MILES	EDGE LINE
621							15.12	2.79	0.10				15.12	0.10	2.79	621	18.01	MILES	LANE LINE
621							6709	1138					6709		1138	621	7847	L.F.	CHANNELIZING LINE
621							280						280			621	280	L.F.	STOP LINE
621							793	251					793		251	621	1044	L.F.	TRANSVERSE LINE
621							29						29			621	29	EACH	LANE ARROW
621							6						6			621	6	EACH	WORD "ONLY" ON PAVEMENT 72 INCH
SPECIAL				1794	330	7							1794	7	330	SPECIAL	2131	EACH	RAISED PAVEMENT MARKER
630										1239	238		1239		238	630	1477	S.F.	SIGN, FLAT SHEET, TYPE G SHEETING
											111				111	630	111	L.F.	GROUND MOUNTED SUPPORT, Nº 2 POST
630										176			176			630	176	L.F.	ONE WAY SUPPORT, Nº 3 POST
630										771	82		771		82	630	853	L.F.	GROUND MOUNTED SUPPORT, Nº 3 POST
630										1048	307		1048		307	630	1355	L.F.	GROUND MOUNTED SUPPORT, Nº 4 POST
630										312			312			630	312	L.F.	GROUND MOUNTED SUPPORT, S4×7.7 BEAM
630											67				67	630	67	L.F.	GROUND MOUNTED SUPPORT, W6×9 BEAM
630										278	39		278		39	630	317	L.F.	GROUND MOUNTED SUPPORT, W10×12 BEAM
630										44			44			630	44	L.F.	GROUND MOUNTED SUPPORT, W8×18 BEAM
630										25.2	3.8		25.2		3.8	630	29	C.Y.	CONCRETE FOR EMBEDDED FOUNDATION
630										38	8		38		8	630	46	EACH	BREAKAWAY BEAM CONNECTION
630										116	25	1	116	1	25	630	142	EACH	REMOVAL OF GROUND MOUNTED SIGN AND STORAGE
630										169	36	1	169	1	36	630	206	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT