

SUPERELEVATION TABLE

MAXIMUM SUPERELEVATION = 0.058 FT/FT AT S.C.

C/L = CENTER LINE

STATION	WESTBOUND					EASTBOUND					COMMENTS
	ELEVATION EDGE OF BERM 64' LT	ELEVATION EDGE OF PAVEMENT 54' LT	ELEVATION C/L PAVEMENT 42' LT	ELEVATION EDGE OF PAVEMENT 30' LT (PROFILE GRADE)	ELEVATION EDGE OF BERM 14' LT	ELEVATION EDGE OF BERM 14' RT	ELEVATION EDGE OF PAVEMENT 30' RT (PROFILE GRADE)	ELEVATION C/L PAVEMENT 42' RT	ELEVATION EDGE OF PAVEMENT 54' RT	ELEVATION EDGE OF BERM 64' RT	
404 + 21.41	653.25	653.46	653.65	653.46	653.13	653.13	653.46	653.65	653.46	653.25	BEGIN TRANSITION - BEGIN ROTATING EB OUTSIDE AND WB INSIDE LANES
404 + 25	653.20	653.41	653.60	653.42	653.09	653.09	653.42	653.61	653.43	653.22	
404 + 50	652.88	653.09	653.28	653.16	652.83	652.83	653.16	653.35	653.23	653.02	
404 + 75	652.55	652.76	652.94	652.88	652.55	652.55	652.88	653.07	653.01	652.80	
405 + 00	652.18	652.39	652.58	652.57	652.24	652.24	652.57	652.76	652.75	652.54	
405 + 02.23	652.14	652.35	652.54	652.54	652.21	652.21	652.54	652.73	652.73	652.52	T.S. - EB OUTSIDE AND WB INSIDE LANES LEVEL
405 + 25	651.78	651.99	652.18	652.23	651.90	651.90	652.23	652.42	652.47	652.26	
405 + 50	651.35	651.56	651.75	651.86	651.53	651.53	651.86	652.05	652.16	651.95	
405 + 75	650.90	651.11	651.30	651.47	651.14	651.14	651.47	651.66	651.83	651.62	
405 + 83.05	650.76	650.97	651.15	651.34	651.01	651.01	651.34	651.53	651.72	651.51	3/16" PER FOOT ACROSS BOTH LANES - BEGIN ROTATING BOTH LANES
406 + 00	650.39	650.60	650.82	651.05	650.72	650.72	651.05	651.28	651.50	651.29	
406 + 25	649.81	650.05	650.34	650.62	650.29	650.24	650.62	650.90	651.19	650.98	
406 + 50	649.20	649.49	649.84	650.18	649.85	649.72	650.18	650.52	650.87	650.66	
406 + 75	648.62	648.95	649.35	649.75	649.42	649.22	649.75	650.15	650.55	650.34	
407 + 00	648.01	648.39	648.85	649.31	648.98	648.70	649.31	649.77	650.23	650.02	
407 + 25	647.42	647.85	648.36	648.88	648.55	648.19	648.88	649.40	649.91	649.70	
407 + 50	646.81	647.29	647.87	648.44	648.11	647.67	648.44	649.01	649.59	649.38	
407 + 75	646.21	646.74	647.38	648.01	647.73	647.17	648.01	648.64	649.28	649.11	
408 + 00	645.61	646.19	646.88	647.57	647.37	646.65	647.57	648.26	648.95	648.83	
408 + 02.23	645.56	646.14	646.83	647.53	647.34	646.61	647.54	648.24	648.93	648.81	S.C. - FULL SUPERELEVATION (0.058 FT/FT)
408 + 30	645.06	646.66	646.35	647.09	646.92	646.24	647.13	647.80	648.65	648.58	END OF PROJECT - MATCH EXISTING PAVEMENT ELEVATIONS
		(MATCH)	(MATCH)	(MATCH)			(MATCH)	(MATCH)	(MATCH)		

SUPERELEVATION TABLE

LAK-2-9.46