



0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31

EXTRA AREA

Merger Begin Project	146	Sq. Yds.
Craneing Road	35	Sq. Yds.
N.S. Sta. 20+75	26	Sq. Yds.
Bishop Rd.	63	Sq. Yds.
Ashmere Rd	15	Sq. Yds.
Total	285	Sq. Yds.

SURFACE - REMOVAL & DISPOSAL

Extra Area	285	Sq. Yds.
Sta. 0+00 to Sta. 31+00 = $3100 \times 8' = 24,800 \text{ Sq. Ft.} \div 9 =$	2755.55	Sq. Yds.
Sta. 0+00 to Sta. 30+65 = $3065 \times 32 = 98,080 \div 9 = 10,897.78$		
Note: * Sta. 30+65 to Sta. 31+00 = $35 \times 34 = 1190 \div 9 = 143.33$		
2% of 11,041.11 =	220.82	Sq. Yds.
Total	326.137	Sq. Yds.

* Note: Surface Course in this area to be removed as directed by the Engineer

MON. BOXES ADJUSTED TO GRADE

2 Each

SEWERS

Catchbasin Casting adjusted to grade 8 Each
Storm Manhole Casting adjusted to grade 3 Each

WATER

Water Manhole Casting adjusted to grade 4 Each
Valve Boxes adjusted to grade 6 Each

700
690
680