



**EXTRA AREA**

Depot Street	22 Sq. Yds.
E. 290 <sup>th</sup> Street	44 Sq. Yds.
E. 291 <sup>st</sup> Street	16 Sq. Yds.
Maple Street	10 Sq. Yds.
Lincoln Ave.	53 Sq. Yds.
Lloyd Road	52 Sq. Yds.
E. 293 <sup>rd</sup> Street	14 Sq. Yds.
Silver Street (N)	16 Sq. Yds.
Silver Street (S)	14 Sq. Yds.
First Ave.	18 Sq. Yds.
E. 294 <sup>th</sup> Street	3 Sq. Yds.
Station Street	55 Sq. Yds.
Rockefeller Ave.	17 Sq. Yds.
<b>Total</b>	<b>334 Sq. Yds.</b>

**SURFACE - REMOVAL & DISPOSAL**

Extra Area	334 Sq. Yds.
Sta. 31+00 to Sta. 62+00 = 3100 x 8' = 24,800 Sq. Ft. ÷ 9	2755.55 Sq. Yds.
* Sta. 31+00 to Sta. 38+60 = 760 x 34' = 25,840 Sq. Ft. ÷ 9 = 2871.11	
* Sta. 38+60 to Sta. 62+00 = 2340 x 32' = 74,880 Sq. Ft. ÷ 9 = 8320.00	
2% of 11,191.11 =	223.82 Sq. Yds.
<b>Total</b>	<b>3,313.37 Sq. Yds.</b>

\*Note: Surface Course in this area to be removed as directed by the Engineer

**WATER**

Water Manhole adjusted to grade	3 Each
Valve Boxes Adjusted to grade	4 Each

**SEWERS**

Catchbasin Casting adjusted to grade	12 Each
Storm Manhole castings adjusted to grade	8 Each
Sanitary Manhole casting adjusted to grade	4 Each

**Mon. Boxes Adjusted To Grade** 3 Each